

15.145-01311-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

NOV 8 1963  
11-8-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Earl Wakefield

Complete Address: 515 Union Center Wichita, Kans

Lease Name Welch Well No. 2

Location Cw $\frac{1}{2}$  W $\frac{1}{2}$  NW Sec. 32 Twp. 22 Rge. (E) (W) 17

County Pawnee Total Depth 4235

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Barnes & Sons & Halliburton Co

Address: Russell, Kans License No. 9

Operation Completed: Hour 4PM Day 5 Month 11 Year 63

The Above well was plugged as follows:

8 5/8" 195' circulated with cement - 5 1/2" 4228' with 125 sax cement -  
Perf 4223'

Filled with sand to 4210', set 4 sax cement with dump bailer - pulled  
3400' 5 1/2" to 600', circulated hole with heavy gel mud through 5 1/2" at 600'  
(20 sax Gel) displaced 20 sax cement through 5 1/2" at 350', heavy mud to  
180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set  
bridge and 10 sax cement to bottom cellar.

Cementing and mudding by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/8/63

INV. NO. 8052-W

Signed: Edwin Lee  
Well Plugging Supervisor