

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

PL

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 11 Twp. 30S Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines C NE NE
Lease Owner O. A. Sutton
Lease Name Figge Well No. 1
Office Address 800 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 27, 1967 19
Application for plugging filed August 27 19 67
Application for plugging approved August 27 19 67
Plugging commenced August 27 19 67
Plugging completed August 27 19 67
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess and Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 2570 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	225	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filed hole with mud to 250', set plug with 1/2 sack hulls and 25 sacks cement. Mud to 40', set plug with 1/2 sack hulls and 8 sacks cement. Plugged rat hole with 2 sacks cement. Complete at 12:00 midnight 8-27-67.

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Inc.
Address 830 Sutton Place, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack G. Paulsen (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen
800 Sutton Place, Wichita, Kansas
(Address)

Sworn to before me this 30th day of August, 19 67.
Jean S. Taylor Notary Public.
Commission Expires June 28, 1970.



15-095-20039-000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1967

REGISTRATION DIVISION
TOPEKA, KANSAS

FIGGE #1
C NE NE SECTION 11-30S-10W
KINGMAN COUNTY, KANSAS

COMMENCED: AUGUST 22, 1967
COMPLETED: AUGUST 26, 1967

OPERATOR - O. A. SUTTON

DEPTH		FORMATION	REMARKS
FROM	To		
0	75	SURFACE CLAY AND SAND	RAN 12 JOINTS 8-5/8" CASING, SET @ 262' w/225 SACKS CEMENT.
75	262	RED BED	
262	790	RED BED	DRY AND ABANDONED.
790	1262	RED BED AND SHALE	
1262	1269	ANHYDRITE	
1269	1595	SHALE AND SHELLS	
1595	1718	LIME AND SHALE	
1718	2050	LIME	
2050	2546	LIME AND SHALE	
2546	2570	SAND	
2570	TD		

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE NE SECTION 11-30S-10W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 29TH DAY OF AUGUST, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.

