

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15-083-20094-0000

Hodgeman County. Sec 32 Twp 21S Rge. (E)24 (W)

Location as "NE/CNW&SW" or footage from lines NE SE

Lease Owner Beardmore Oil Inc.

Lease Name KLINE "A" Well No. 1

Office Address 700 One Twenty Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-11 19 69

Application for plugging filed 10-11 19 69

Application for plugging approved 10-11 19 69

Plugging commenced 10-11 19 69

Plugging completed 10-11 19 69

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eaves, Sublette, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	549'	-0-

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud back to 550'. Spotted 35 sacks cement. Mud back to 40', set solid bridge and 15 sacks cement. Job completed at 10:45 AM 10-11-69.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of October, 19 69

My commission expires 6-30-71

Sherry Gish
Sherry Gish Notary Public.

ROTARY DRILLING LOG

15-083-20094-0000 ^{9B}

Operator: Beardmore Oil Inc.
KLINE "A" #1
NE SE Section 32-21S-24W
Hodgeman County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 9-30-69
Completed: 10-11-69

Casing: 8-5/8" @ 549'/275 sx.
common cement.

Formations

Shale and Sand	240'
Shale	1004'
Blaine Anhydrite	1011'
Shale and Sand	1035'
Shale	1123'
Sand	1330'
Shale	1649'
Anhydrite	1685'
Shale	1845'
Shale and Lime	2325'
Lime	2340'
Lime and Shale	2460'
Lime	2830'
Lime and Shale	3970'
Lime	4600'
Rotary Total Depth (D & A)	4600'


RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 13 day of October, 1969.


Sherry Gish Notary Public

My Commission Expires:
6-30-71