

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

OCT 12 1982

Form CP-4  
Rev. 12-15-80

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD Operator No. 5447

Give All Information Completely  
Make Required Affidavit

COUNTY Kingman SEC. 15 TWP. 30S RGE. 10 W/W  
Location as in quarters or footage from lines:  
1320' FNL - 1320' FEL


Locate Well  
correctly on above  
Section Platt.

Lease Owner Cities Service Company  
Lease Name Depenbusch "B" Well No. 1  
Office Address 209 E. William, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
Date Well Completed October 1, 1979  
Application for plugging filed July 6, 1982  
Plugging commenced September 22, 1982  
Plugging completed September 24, 1982  
Reason for abandonment of well or producing formation Uneconomical for production

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie

Producing formation Indian Cave Depth to top 2600' bottom 2604' T.D. 2665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				7"	271'	- 0 -
				4 1/2"	2664'	1359'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Put sand on bottom and 4 sacks cement plug to 2550 ft. Pulled 1359 ft. (34 jts) of 4 1/2" OD 9.5# casing. Plugged with 15 sacks gel, 6 sacks of hulls, 10 sacks gel. Released 7" plug and cemented with 100 sacks of 50/50 pozmix with 4% gel and 3% CaCl-2. Total 630' of fillup. Plug and abandonment completed 9/24/82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

W. J. Devaney (~~owner~~ ~~operator~~) (employee of owner) or (~~owner~~ ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

**VANORA E. DAY**  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appointment Expires:  
2-23-85

(Signature) W. J. Devaney  
800 Sutton Place Bldg,  
209 E. William, (Address) Wichita, Ks.  
67202

SUBSCRIBED AND SWORN TO before me this 8 day of October, 19 82

Vanora E. Day  
Notary Public.

My Commission expires: 2-23-85

Vanora E. Day

15-095-20869-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED Form CP-4  
Rev. 12-15-80  
STATE CORPORATION COMMISSION

SEP 28 1982

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kingman SEC. 15 TWP. 30 RGE. 10W E/W  
Location as in quarters or footage from lines:  
1320' FEL 1320' FNL NE/4


Lease Owner Cities Service Oil Company  
Lease Name Epenbusch A-1 Well No. \_\_\_\_\_  
Office Address Box 266 St. John, Kansas 67576  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 9-20-82  
Plugging completed 9-24-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 2665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				7"	271'	none
				4-1/2"	2664'	1359'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 2550' and ran 4 sacks cement. Shot casing @1702', 1623', 1501', 1383' and pulled a total of 34 joints of 4-1/2" casing. Plugged well with 15 gel, 6 hulls, 10 gel, plug and 100 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 82

My Commission expires: 

Irene Hoover  
Notary Public.

15-095-20869-0000

Operator Cities Service Oil Co. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDOW, ETC.: Gas

Well No. "B" #1 Lease Name Depenbusch

S 15 T 30 R 10 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
soil	0	33		
shale/lime	33	245		
lime/shale	245	334		
sand/shale	334	609		
sand	609	763		
sand/shale	763	1130		
shale	1130	1545		
lime	1545	1560		
sand	1560	1588		
lime	1588	1597		
lime/shale	1597	1617		
shale	1617	1620		
lime/shale	1620	1980		
sand	1980	2001		
lime	2001	2017		
shale	2017	2065		
lime	2065	2070		
shale	2070	2073		
shale/lime	2073	2240		
lime	2240	2290		
shale/lime	2290	2665		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p><i>W. J. Devaney</i> Signature W. J. Devaney Region Operations Manager Title 10-5-79 Date</p>
---------------	--