

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County. Sec. 15 Twp. 22S Rge. 11 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner WESTERN PETROLEUM CO., INC.

Lease Name SHEPPARD Well No. 1

Office Address 925 PATTON ROAD, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed NOVEMBER 14 1960

Application for plugging filed NOVEMBER 14 1960

Application for plugging approved NOVEMBER 14 1960

Plugging commenced 10:00 P.M. NOVEMBER 14 1960

Plugging completed 3:00 A.M. NOVEMBER 15 1960

Reason for abandonment of well or producing formation DRY HOLE.

If a producing well is abandoned, date of last production - - - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT, ST. JOHN, KANSAS.

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH DRILLING MUD TO 270', CEMENTED FIRST PLUG AT 270' WITH 20 SACKS COMMON CEMENT. CEMENTED SECOND PLUG AT 40' WITH 10 SACKS COMMON CEMENT TO SURFACE.

11-18-60

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WESTERN PETROLEUM CO., INC.

Address 925 PATTON ROAD, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.

GEORGE B. TURNER (employee of owner) ~~NOT A SWORN OFFICER~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George B Turner

925 PATTON ROAD, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 15TH day of NOVEMBER, 19 60

My commission expires AUGUST 5, 1964

Luella F. Dwyer Notary Public.



DRILLER'S LOG

COMPANY: WESTERN PETROLEUM Co., INC. LOCATION: SW SW NE
 CONTRACTOR: WESTERN PETROLEUM Co., INC. SECTION 15, T22S, R11W
 STAFFORD COUNTY, KANSAS
 FARM NAME: SHEPPARD ELEVATION: 1783' K.BY.
 COMMENCED: NOVEMBER 2, 1960 CASING USED: 8-5/8" AT 270' WITH 225 SACKS
 COMPLETED: NOVEMBER 15, 1960

SAND	40
SAND, CLAY	70
RED BED	478
ANHYDRITE	502
SHALE	1285
SHALE & LIME	1585
LIME & SHALE	1920
SHALE & LIME	2320
LIME & SHALE	2520
SHALE & LIME	2645
LIME & SHALE	2958
LIME	3057
SHALE	3210
LIME	3485
LIME & CHERT	3512
LIME	3541
LIME & SHALE	3577
LIME	3633
TOTAL DEPTH	3633

RECEIVED
 STATE GEOLOGICAL COMMISSION
 NOV 18 1960
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

George B. Turner
 GEORGE B. TURNER, DRLG. SUPT.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16TH DAY OF NOVEMBER, 1960.

Luella F. Dwyer
 LUELLA F. DWYER, NOTARY PUBLIC

MY COMMISSION EXPIRES: AUGUST 5, 1964.