

API NUMBER 15-083 20,185-0000

LEASE NAME Schauvliege "B"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Coas. Div.
 office within 30 days.

WELL NUMBER 2

1880 Ft. from ^N Section Line

1930 Ft. from E Section Line

LEASE OPERATOR Vintage Petroleum, Inc.

SEC. 6 TWP. 22 RGE. 24 (E) r (W)

ADDRESS 4200 One Williams Center, Tulsa, OK 74172

COUNTY Hodgeman

PHONE# (918) 592-0101 OPERATORS LICENSE NO. 3122

Date Well Completed 10/71

Character of Well Good

Plugging Commenced 3/30/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3/30/95

The plugging proposal was approved on March 30, 1995 (date)

by Mr. Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? filed with form CP-1 1/30/95

Producing Formation Mississippi Dolomite Depth to Top 4577 Bottom 4584 T.D. 4670

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Oil	Ø Surf	600	8 5/8	600'	None
		Ø Surf	4669	4 1/2	4669'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set
Pump 100 sxs cmt 60-40 POZ cmt down annulus. Pump 225 sxs down 4 1/2 csg. & pressure up to 500#. One week later surface pipe was cut off 5' below ground level and capped.

Name of Plugging Contractor Halliburton

License No. 5287 RECEIVED STATE CORPORATION COMMISSION MAY 3 1995 WICHITA, KANSAS

Address Hays, KS P.O. Box 428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vintage Petroleum, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Rebecca Sanford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Rebecca Sanford

(Address) 4200 One Williams Center, Tulsa, OK 74172

SUBSCRIBED AND SWORN TO before me this 26 day of April, 19 95

Delese Arnold
 Notary Public

USE ONLY ONE SIDE OF EACH FORM
 My Commission Expires: 11/7/99