

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083 20,198-0000

LEASE NAME Schauvliege "B"

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1890 Ft. from S/N Line of Section (circle one)

760 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR Vintage Petroleum, Inc.

SPOT LOCATION C - SE - NE -

ADDRESS 4200 One Williams Center

SEC. 6 TWP. 22 S. RGE 24 (E) or (W)

CITY, STATE, ZIP Tulsa, OK 74172

COUNTY Hodgeman

PHONE#(918) 592-0101 OPERATORS LICENSE NO. 03122

Date Well Completed 10-7-71

Charater of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 4-6-95

Date Plugging Completed 4-6-95

The plugging proposal was approved on March 30, 1995 (date)
by Mr. Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? unknown If not, is well log attached? Filed with Form CP-1 1/30/95

Producing Formation(s) Mississippi Depth to Top 4541 Bottom 4546 T.D. 4625

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Mississippi	Oil	Surface	590	8 5/8	590	None
		Surface	4624	4 1/2	4624	None

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pump 250# cottonseed hulls & 25 sxs 60-40 POZ cmt down tbq from 4405 to 3905.
Place 20 sxs Gel from 3905 to 890; pump 50 sxs 60-40 POZ thru perfs @ 890'. Pmp
50 sxs cmt down 4 1/2". pmp 175 sxs cmt down 8 5/8" pressure up to 400#. One wk
later surface pipe was cut off 5' below ground level and capped.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton

RECEIVED
KANSAS CORPORATION COMMISSION

License No. 5287

JUN 28 1995

Address P.O. Box 428, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vintage Petroleum, Inc.

CONSERVATION DIVISION
WICHITA, KS

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Rebecca Sanford (Employee of Operator or (Operator) of above-described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Rebecca Sanford

(Address) 4200 One Williams Center, Tulsa, OK, 74172

SUBSCRIBED AND SWORN TO before me this 27 day of June, 19 95

Helen Arnold
Notary Public

My Commission Expires: 1-17-99