


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Hodgeman County. Sec. 6 Twp. 22S Rge. 24W (E) (W)
Location as "NE/CNW&SW" or footage from lines 150' East of C SE SE
Lease Owner Donald C. Slawson
Lease Name Dixon 'E' Well No. 1
Office Address Suite 408 One Twenty Building-Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 6, 1971
Application for plugging filed October 6, 1971
Application for plugging approved October 6, 1971
Plugging commenced October 6, 1971
Plugging completed October 6, 1971
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves-P.O. Box 'F'-Sublette, Kansas 67866
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	584'	8 5/8"	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 650'; set plug; 50 sx cement
Mud to 40'; bridge; 15 sx cement
2 sx cement in rat hole

Completed at 2:15 p.m., October 6, 1971

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.
Address Suite 408 One Twenty Building - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.


Margie V. Starr (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
408 One Twenty Building - Wichita, Kansas
(Address)

Subscribed and sworn to before me this 18th day of October, 1971

My commission expires May 15, 1975

[Signature]
Linda R. Mitchell
Notary Public.



WELL LOG

Company: Donald C. Slawson
 Suite 408 One Twenty Building
 Wichita, Kansas 67202

Lease: Dixon 'E' #1
 150' East of C SE SE, Section 6-22S-24W
 Hodgeman County, Kansas

Total Depth: 4600' Elevation: 2422 K.B.

Contractor: Slawson Drilling Company, Inc.

Commenced: September 28, 1971

Completed: October 6, 1971

Casing: 8 5/8" at 584' with 275 sx cement

0-384	Surface Clay
384-1614	Shale & Shells
1614-1650	Anhydrite
1650-2610	Shale & Lime
2610-4043	Lime & Shale
4043-4600	Lime
4600	Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 19 1971
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, Maxine V. Starr, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Dixon 'E' #1 well.

Maxine V. Starr
 MAXINE V. STARR

Subscribed and sworn to before me this 18th day of October, 1971.

Linda R. Mitchell
 Linda R. Mitchell, Notary Public

