


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County, Sec. 6 Twp. 22S Rge. 24W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 150' NE of NW SE

Lease Owner Rains & Williamson Oil Co., Inc.
Lease Name Dixon Well No. 1
Office Address 435 Page Court, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 8-21 1976
Application for plugging filed 8-21 1976
Application for plugging approved 8-21 1976
Plugging commenced 8-21 1976
Plugging completed 8-21 1976

Reason for abandonment of well or producing formation
No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4600
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surf	606	8-5/8"	598	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 900', plug, 35 sx cement;
Fluid to 600', plug, 35 sx cement;
Fluid to 40', plug, 15 sx cement;
Five sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1976

CONSERVATION DIVISION
Wichita, Kansas

8-30-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 19 76

Ella Priess

My commission expires 8-25-80

Ella Priess

Notary Public.



DRILLERS' LOG

RAINS & WILLIAMSON OIL CO., INC.
Dixon No. 1
150' NE of NW SE, Sec. 6-22S-24W
Hodgeman County, Kansas

Elev: 2446 K.B.

Commenced: 8-14-76
Completed: 8-21-76

Surface Casing: 598' of
8-5/8" cemented w/300 sx
common cement, 2% Gel,
3% cc. 8-15-76

FORMATION

DEPTH

Surface Hole	0 - 606
Shale	606 - 1115
Sand, Red Bed & Shale	1115 - 1638
Anhydrite	1638 - 1673
Shale	1673 - 2320
Shale & Lime	2320 - 2630
Lime & Shale	2630 - 2880
Shale & Lime	2880 - 3395
Lime & Shale	3395 - 4080
Lime	4080 - 4600 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 26th day of August, 1976.

Ella Priess

Ella Priess, Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1976

CONSERVATION DIVISION
Wichita, Kansas

ELLA PRIESS
Sedgwick County, Ks.
My Appl. Exp. Aug. 25, 1980