

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Hodgeman County, Sec. 4 Twp. 22S Rge. (E) 24 (W)  
Location as "NE/CNW/SW" or footage from lines C/NE SW  
Lease Owner Petroleum, Inc.  
Lease Name Gumbir Well No. 1  
Office Address 300 West Douglas, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 21 19 73  
Application for plugging filed July 21 19 73  
Application for plugging approved July 21 19 73  
Plugging commenced July 21 19 73  
Plugging completed July 21 19 73  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette  
Producing formation Depth to top Bottom Total Depth of Well 4698 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	295.06'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Plugged hole as follows: Plugged at 500' with 80 sacks of common cement; plugged at 45' with 15 sacks of common cement & hulls. Plug down at 4:15 P. M. July 21, 1973.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 25 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON ss.  
Charles W. Steincamp (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STRATA DRILLING, INC.

(Signature) Charles W. Steincamp  
Charles W. Steincamp, President  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)



Subscribed and sworn to before me this 23rd day of July, 19 73  
December 14, 1973  
Elaine H. Taylor Notary Public.

DRILLERS LOG

#1 Gumbir

CASING RECORD:  
290.06 of new 8-5/8"  
surface casing.

COMPANY: Petroleum, Inc.  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/NE SW  
Section 4-22S-24W  
Hodgeman County, Kansas

TOTAL DEPTH:  
4698'

COMMENCED: July 10, 1973  
COMPLETED: July 21, 1973

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Shale	0	410	Ran 290.06' of new 8-5/8" surface casing; set and cemented at 295.06' with 225 sacks of common cement, 2% gel and 3% C. C. Plug down at 12:10 A. M. July 11, 1973.
Shale	410	1466	
Shale & Sand	1466	1876	
Shale & Lime	1876	3580	
Lime	3580	3745	
Lime & Shale	3745	4110	
Lime	4110	4213	
Lime & Shale	4213	4355	
Lime	4355	4429	
Lime & Shale	4429	4565	
Lime	4565	4618	
Shale & Lime	4618	4658	
Lime	4658	4678	
Lime & Shale	4678	4698	

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 25 1973  
CONSERVATION DIVISION  
Wichita, Kansas

ROTARY TOTAL DEPTH: 4698'

Ran three drill stem tests.

Ran electric log.

D. & A.

Plugged hole as follows: Plugged at 500' with 80 sacks of common cement; plugged at 45' with 15 sacks of common cement & hulls. Plug down at 4:15 P. M. July 21, 1973.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 23rd of July, 1973.

My Commission Expires:  
December 31, 1977

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

