

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 4 Twp. 22S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner Rains & Williamson Oil Co.

Lease Name GUMBIR Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-22 19 63

Application for plugging filed 10-22 19 63

Application for plugging approved 10-22 19 63

Plugging commenced 10-22 19 63

Plugging completed 10-22 19 63

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production --- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas

Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4815 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	248'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Set plug at 600'. Cemented through drill pipe with 20 sacks cement. Filled hole with rotary mud to 240'. Set second plug with 1/4 sack hulls and cemented through drill pipe with 20 sacks cement. Filled hole with rotary mud to within 40' of base of cellar. Cemented 1/4 sack hulls, capped with 10 sacks cement. Plugging completed at 10:30 A.M. 10-22-63.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION
Wichita, Kansas

10-28-63

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Building - Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Wilson Rains, Partner

(owner or operator) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza - Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 25th day of October, 19 63

My commission expires November 8, 1966
Sherry Gish Notary Public.



ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co.
and Mull Drilling Co., Inc.
#1 GUMBIR
C SE SE Sec. 4-22S-24W
Hodgeman County, Kansas

CONTRACTOR: Rains & Williamson
Oil Co.
COMMENCED: 10-9-63
COMPLETED: 10-22-63

Remarks: Set 8-5/8" casing at
248' with 130 sacks
quick cement.

Formations

Surface Soil and Clay	50'
Sand	80'
Shale	252'
Shale and Red Bed	430'
Sand	560'
Shale, Red Bed, Sand Streaks	1250'
Sand	1405'
Shale and Red Bed	1730'
Anhydrite	1764'
Shale and Shells	1950'
Shale and Lime Shells	2155'
Shale and Lime Streaks	2415'
Lime	2480'
Lime and Shale	2730'
Lime	2940'
Shale and Lime	3035'
Lime	3240'
Shale and Lime	3292'
Lime	4815'
Rotary Total Depth (D&A)	4815'

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963


CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.


Wilson Rains
Partner

Subscribed and sworn to before me, a
Notary Public within and for the State
of Kansas, County of Sedgwick, this 24th
day of October, 1963.


Sherry Gish Notary Public

My Commission Expires:
November 8, 1966