

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

15-009-03100-0001 WELL PLUGGING APPLICATION FORM
PLEASE TYPE FORM and File ONE Copy)

API # 1941 (Identifier number of this well) This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Cla-Mar Oil Company KCC LICENSE # 6509 ^{1/98}
(owner/company name) (operator's)

ADDRESS PO Box 1197 CITY Hays

STATE Kansas ZIP CODE 67601 CONTACT PHONE # (913) 625-3863

LEASE Esfeld WELL# 6SWD SEC. 28 T. 16 R. 11 (East West)

C - SW - SE - SE SPOT LOCATION/QQQQ COUNTY Barton

330 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# 82,054-C

CONDUCTOR CASING SIZE NA SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 10" SET AT 765' CEMENTED WITH 35sx SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 3389' CEMENTED WITH 35sx SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: OH 3437'-3610'

ELEVATION 1927 T.D. 3610' PBSD _____ ANHYDRITE DEPTH 759'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Pump 75sx 60/40 poz 10% gel and 200# hulls down tubing to plug bottom. Let set up.

Blow tubing @ approx 2000 ft. Circulate with 60/40 poz 10% gel and 500# hulls to surface.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jim Clark PHONE # (913) 625-3863

ADDRESS PO Box 1197 City/State Hays KS 67601

PLUGGING CONTRACTOR Allied Cementing Company, Inc KCC LICENSE # _____
(company name) (contractor's)

ADDRESS PO Box 31, Russell KS 67665-031 PHONE # (913) 483-2627

PROPOSED DATE AND HOUR OF PLUGGING (If Known?), _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5-1-97 AUTHORIZED OPERATOR/AGENT: _____

(signature)

4



Kansas Corporation Commission

*Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel*

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

May 8, 1997

Cla-Mar Oil Company
P O Box 1197
Hays KS 67601

Esfeld #6 SWD
API 15-N/A
330 FSL 990 FEL
Sec. 28-16S-11W
Barton County

Dear Jim Clark,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #4
2301 E 13th
Hays KS 67601
(913) 628-1200