


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 2 Twp. 22S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines. Approx. C SW NW
Lease Owner Chief Drilling Co., Inc.
Lease Name HARPER Well No. 1
Office Address Box 797 - Gt. Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/23/1965
Application for plugging filed 11/23/1965
Application for plugging approved 11/23/1965
Plugging commenced 11/23/1965
Plugging completed 11/23/1965
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman - Holyrood, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	199'	8-5/8"	199'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/4 sack hulls & wooden plug set @ 190'
Mixed 25 sacks cement through drill pipe
1/2 sack hulls & wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe
Cemented rat hole with 2 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1965
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Chief Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Box 797 - Gt. Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CHIEF DRILLING CO., INC.

(Signature) *V. Richard Hoover*
Box 797 - Gt. Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of November, 1965

My commission expires Jan. 26, 1967

Carmen R. Cook
Carmen R. Cook, Notary Public.

REWELE LOG
STATE CORPORATION COMMISSION

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

NOV 24 1965

HARPER #1
C SW NW Sec. 2-22S-8W
Rice County, Kansas

Contractor: German Drilling Co. Wichita, Kansas

Commenced: 11-15-65
Completed: 11-23-65

Casing Record: 8-5/8" @ 199' w/ 200 sacks Sunset, 2% Gel.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand	0	35	1622 Gr.
Gravel	35	50	1624 D.F.
Sand & Shale	50	130	1628 K.B.
Red Bed & Shale	130	160	
Shale	160	204	
Red Bed	204	230	
Shale	230	1080	
Anhydrite	1080	1130	
Shale & Lime	1130	2944	
Lime	2944	3396	
Conglomerate	3396	3403	
Lime & Chert	3403	3416	
Shale	3416	3430	
Total Depth	3430		

<u>FORMATION TOPS</u>			
Anhydrite	1080	+ 548	
Heebner	2796	-1168	
Douglas	2820	-1192	
Brown Lime	2944	-1316	
Lansing	2975	-1347	
Conglomerate	3396	-1768	
Mississippian	3403	-1775	
Kinderhook Shale	3416	-1788	
Total Depth	3430	-1802	

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW NW of Section 2-22S-8W, Rice County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Richard Hoover
V, Richard Hoover, President

Subscribed and sworn to before me this 23rd day of November, 1965.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.