

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 21 Twp. 22S Rge. (E) 8 (W)

Location as "NE/CNWKSWK" or footage from lines C NE SE
Lease Owner Sterling Drilling Company, et al
Lease Name Carris Well No. 1
Office Address Box 127, Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 24, 1962 19
Application for plugging filed August 24, 1962 19
Application for plugging approved August 24, 1962 19
Plugging commenced August 25, 1962 19
Plugging completed August 25, 1962 19
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Herman Justus
Producing formation Depth to top Bottom Total Depth of Well 3663' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	@ 210'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging orders by Mr. Herman Justus. Set Halliburton plug at 180' 1/4 sack hulls on plug, 20 sacks cement through drill pipe. Heavy mud up to 35' Halliburton plug at 35' 1/4 sack hulls on plug, 8 sacks cement up to base cellar. 2 sacks cement in rat hole. Started plugging 4:15 A. M., 8-25-62, plugging complete @ 6:30 A. M., 8-25-62

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1962
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company
Address Box 127, Sterling, Kansas

9-10-62

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. A. Wuellner*
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of August, 1962

My Commission Expires Jan. 22, 1966
BERNARD LAUDERMILK

Bernard Laudermilk
Bernard Laudermilk Notary Public.

My commission expires



GROUP EXPLORATION COMPANY
Sterling, Kansas

WELL LOG ----- Carris #1
Located: C NE SE of Section 21-22S-8W, Reno County, Kansas

OWNER: Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 8-17-62
COMPLETED: 8-25-62

ROTARY TOTAL DEPTH: 3663'

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1962

CONSERVATION DIVISION
Wichita, Kansas

LOG

0	--	213	Shale & Sand
213	--	265	Red Bed
265	--	1190	Shale & Shells
1190	--	1510	Shale & Lime
1510	--	1850	Lime
1850	--	2030	Shale & Lime
2030	--	2355	Shale
2355	--	2515	Shale & Lime
2515	--	2885	Lime
2885	--	3070	Lime & Shale
3070	--	3565	Lime
3565	--	3587	Lime & Chat
3587	--	3620	Conglomerate
3620	--	3663	Lime & Shale

T.D.

CASING RECORD

Set 8 5/8" Surface Casing @ 210'
with 175 sacks Pozmix with HA-5.

Plugged & Abandoned.