


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 5 Twp. 22 Rge. 11 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NE  
Lease Owner. Frontier Oil Company  
Lease Name. Fair Well No. 1  
Office Address. 580 4th Nat'l Bank Bldg. - Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed February 25 1959  
Application for plugging filed February 25 1959  
Application for plugging approved February 25 1959  
Plugging commenced February 25 1959  
Plugging completed February 25 1959  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	229'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 200'. Set  
bottom plug @ 200', with 20 sx cement  
and 1/4 sx hulls. Filled with heavy  
mud. Set top plug @ 35' w/10 sx cement  
and 1/2 sx hulls. Filled to base of  
cellar.

3-3-59

RECEIVED  
STATE CORPORATION COMMISSION

MAR 3 1959

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
Address Box 173 - Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
George A. Angle

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

580 4th Nat'l Bank Bldg. - Wichita  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of February, 1959

Margie Head

Notary Public.

My commission expires 11-17-62



PLUGGING  
FILE SEC 5 T 22 R 11W  
BOOK PAGE 19 LINE 12

DRILLERS LOG

No. 1 Fair

CASING RECORD: 8 5/8" @ 229\*  
w/175 sx cement

COMPANY: Frontier Oil Company

CONTRACTOR: Red Tiger Drilling Co.

DESCRIPTION: SW SW NE  
5-22S-11W  
Stafford County,  
Kansas

COMMENCED: February 16, 1959

TOTAL DEPTH: 3567 (-1812)

COMPLETED: February 25, 1959

ELEVATION: 1752 DF  
1755 RB

FORMATION	FROM	TO	REMARKS
Sand	0	25	
Shale and Shells	25	229	
Red Bed Shale and Shells	229	495	
Anhydrite	495	528	
Shale and Shells	528	880	
Shale, Shells and Salt	880	1200	
Shale and Shells	1200	1350	
Shale and Lime	1350	1815	
Shale and Shells	1815	1895	
Shale and Lime	1895	2940	
Lime	2940	2970	
Lime and Shale	2970	3165	
Lime	3165	3465	
Conglomerate	3465	3491	
Cherty Conglomerate	3491	3515	
Conglomerate	3515	3536	
Arbuckle	3536	3567	

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 3 1959  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above  
log to the best of my knowledge.

FRONTIER OIL COMPANY

*George A. Angle*  
George A. Angle

Subscribed and sworn to before me this 27th day of February, 1959.

*Minnie Head*  
Notary Public

My Commission Expires:  
11-17-62

PLUGGING  
FILE SEC 5 T. 22 R. 11W  
BOOK PAGE 19 LINE 12