


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 21 Twp. 30 Rgo. 10 W (E) (W)

Location as "NE/CNWSW" or footage from lines C SW SW
Lease Owner Comet Petroleum Corporation
Lease Name Hudson Well No. 1
Office Address 608 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 9 1969
Application for plugging filed June 9 1969
Application for plugging approved June 9 1969
Plugging commenced June 9 1969
Plugging completed June 9 1969
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4742 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud to 240' from surface, 1/2 sack of hulls, plug and 25 sacks of cement. Fill hole with heavy mud to 40' of surface, 1/2 sack of hulls, plug and 10 sacks of cement. Put 2 sacks of cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Don Gardner (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
300 Schweiter Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1969

My commission expires December 14, 1969

Notary Public.

DRILLERS LOG

#1 HUDSON
C SW SW Section 21-30S-10W
Kingman County, Kansas

OPERATOR: Comet Petroleum Corporation
608 Union Center
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
300 Schweiter Building
Wichita, Kansas

COMMENCED: May 28, 1969

COMPLETED: June 8, 1969

CASING RECORD: 8-5/8" @ 240' w/250 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	40	Sand, clay
40	240	Clay, sand, Red Bed
240	1400	Shale and shells
1400	1915	Lime shells, shale
1915	2300	Lime
2300	3190	Lime and shale
3190	3500	Lime
3500	3828	Lime and shale
3828	4388	Lime
4388	4416	Shale and lime
4416	4483	Lime
4483	4668	Shale
4668	4735	Lime
4735	4742	Sand
4742		Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)


I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


Don Gardner

Subscribed and sworn to before me this 9th day of June, 1969.

My commission expires:
December 14, 1969


Notary Public