


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 7 Twp. 22 Rge. 11 (E) (W)
Location as "NE/CNW/4SW 1/4" or footage from lines SE SE NE
Lease Owner Westgate-Greenland Oil Company
Lease Name Wolf Well No. 1
Office Address 1022 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed June 23, 1949 19
Application for plugging filed Orally-June 23, 1949 19
Application for plugging approved written June 27, 1949 19
Plugging commenced June 23, 1949 19
Plugging completed June 23, 1949 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	282	8 5/8"	282	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3729 to 280'
Set plug at 280' and run 15 sacks cement to 230'
Filled hole with heavy mud to 25' and ran 10 sacks
cement to cellar base

RECEIVED
CONSERVATION DIVISION
JUN 27 1949
STATE CORPORATION COMMISSION

6-28-49

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company c/o G. E. Bitler
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1022 Union National Bank Building, Wichita 2, Ks
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of June, 1949.
Esther Russell
Notary Public.

My commission expires May 25, 1949 1953



COMPANY: Westgate Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Wolf #1
 LOCATION: SE SE NE Section 7-22-11W
 Stafford County, Kansas
 ELEVATION: 1802
 COMMENCED: June 10, 1949
 COMPLETED: June 23, 1949

0	to	110	Sand
110	to	215	Shale & shells
215	to	530	Red bed
530	to	565	Lime
565	to	700	Red bed and shale
700	to	1200	Shale & shells
1200	to	1280	Shale
1280	to	1640	Shale & shells
1640	to	1680	Lime
1680	to	2345	Lime & shale
2345	to	2540	Shale & salt
2540	to	2870	Shale & shells
2870	to	3170	Lime
3170	to	3211	Shale
3211	to	3228	Shale & Lime
3228	to	3233	Lime
3233	to	3270	Lime & shale
3270	to	3570	Lime
3570	to	3621	Lime & red bed
3621	to	3650	Red bed & shale
3650	to	3680	Cherty & shale
3680	to	3729	Arbuckle
		3729 T.D.	

RECEIVED

8 5/8" - 32# casing set at 282 feet. Cemented with 275 sacks cement.

Top Arbuckle 3700

Dry and abandoned

Measurements taken from top of derrick floor

JUN 28 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Wolf #1, Section 7-22-11W, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 27th day of June, 1949.

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November 30, 1950

