


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Exting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County, Sec. 7 Twp. 22S Rge. 11W (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW
Lease Owner Stearns Petroleum, Inc.
Lease Name Wolf Well No. "B"1
Office Address Box 313, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed June 27, 1956 19 56
Application for plugging filed June 27, 1956 19
Application for plugging approved June 27, 1956 19 56
Plugging commenced 1:00 p.m. June 27, 1956 19 56
Plugging completed June 27, 1956 19
Reason for abandonment of well or producing formation Dry and abandoned

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. L. Brundridge
Producing formation None Depth to top Bottom Total Depth of Well 3665 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with drill mud to surface pipe, HOWCO plug with 1/3 sacks hulls on top of plug at 210' with 25 sacks cement through drill pipe.
Mud to 35'
HOWCO plug with 1/3 sacks hulls and plug with 10 sacks cement to surface

6-29-56

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1956
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stearns Petroleum, Inc.
Address Box 313, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
R. V. Appling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. R. V. Appling, Field Supt.

(Signature) [Signature]
Box 313, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1956

My commission expires April 5, 1958 Betty Lou Miller Notary Public.

PLUGGING
FILE SEC 7 T 22 R 11W
BOOK PAGE 75 LINE 13

WOLF "B" 1

Operator: Stearns Petroleum, Inc.
 Contractor: Stearns Petroleum, Inc.
 Commencement Date: June 12, 1956
 Completion Date: June 27, 1956
 Elevation: 1813' K. B.
 I. P.: D. & A.

Location:
 NW SE SW
 Section 7-22S-11W
 Stafford County, Kansas

Surface Casing: 5 joints 8-5/8" casing set at 202 feet with 175 sacks Pozmix and 3 sacks Calcium Chloride. Cement circulated.

WELL LOG

Sand & Clay	0	40
Sand & Shale	40	100
Red Bed and Shale	100	202
Shale & Shells	202	215
Red Bed	215	550
Anhydrite	550	579
Shale & Shells	579	605
Shale	605	650
Shale & Sand	650	810
Shale & Shells	810	1476
Shale & Lime	1476	3255
Lime	3255	3565
Chert	3565	3580
Lime	3580	3665
R. T. D.	3665	

Tops:

Anhydrite	550	(-1263)
Brown Lime	3231	(-1418)
Lansing Kansas City	3255	(-1442)
Conglomerate	3505	(-1692)
Viola	3531	(-1718)
Simpson	3558	(-1745)
Arbuckle	3634	(-1821)
Total Depth	3665	(-1852)

STATE OF KANSAS)
) SS:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

O. G. Stearns, President

SUBSCRIBED AND SWORN TO BEFORE ME, a Notary Public this 28th day of June, 1956

Betty Lou Miller
 Betty Lou Miller, Notary Public

My Commission Expires: April 5, 1958

PLUGGING
 FILE SEC 7 T 22 R 11W
 BOOK PAGE 75 LINE 13