

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 7 Twp. 22 Rge. (E) 11 (W)

Location as "NE/CNW%SW%" or footage from lines N/2 SW SW

Lease Owner Icer Addis

Lease Name Wolf Well No. 1

Office Address Box 519 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed Dec. 4 1960

Application for plugging filed Dec. 8 1960

Application for plugging approved 19

Plugging commenced Dec. 4 1960

Plugging completed " " 1960

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3636 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 240', 1/4 sack of hulls and 20 sacks of cement, Top plug at 35', with 1/2 sack of hulls and 10 sacks of cement.

12-9-60

STATE CORPORATION COMMISSION
DEC. 9 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Triangle Drilling, Inc.
Address Box 519 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Donald D. Vaughan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D. Vaughan
Box 619 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th. day of December, 19 60

My commission expires July 1, 1964
Jessie Lee Dunn, Notary Public.



WELL LOG

COMPANY Icer Addis
 CONTRACTOR Triangle Drilling, Inc.
 FARM #1 Wolf
 LOCATION N/2 SW SW of Section 7-22-11W
 Stafford County, Kansas
 ELEVATION 1811 KB
 SURFACE PIPE 8 5/8" cemented @ 248' w/230 sacks HA5 cement
 PRODUCTION D & A
 COMMENCED November 25, 1960
 COMPLETED December 4, 1960

<u>FORMATION</u>	<u>DEPTH</u>
Sand	105
Red clay & shale w/sand streaks	248
Red bed	551
Anhydrite	571
Shale and shells	1300
Lime and shale	2855
Limestone	3118
Shale	3216
Limestone	3507
Conglomerate	3517
Chert	3554
Shale	3574
Dolomite	3585
Shale	3610
Dolomite	3636

RECORDED
 INDEXED
 DEC 9 1960
 COMMISSIONER OF REVENUE
 Topeka, Kansas

FORMATION TOPS

Anhydrite	551	(-1260) driller's
Heebner	3085	(-1274)
Toronto	3106	(-1295)
Brown Lime	3216	(-1405)
Lansing	3242	(-1431)
Chert Conglomerate	3507	(-1696)
Viola	3517	(-1706)
Simpson	3554	(-1743)
Simpson dolomite	3579	(-1768)
Arbuckle	3610	(-1799)
RTD	3636	(-1825)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON, SS.

I, Donald D. Vaughan, Petroleum Geologist, being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan

 Donald D. Vaughan

Subscribed and sworn to before me this 6th day of December, 1960.

Donna Lea Foelgner

 Donna Lea Foelgner
 Notary Public

My commission expires: May 11, 1963.