


Give All Information Completely  
State Required Affidavit  
Map or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Hamilton County. Sec. 25 Twp. 24S Rge. 41W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NW  
Lease Owner Livingston Oil Company  
Lease Name Unit 2541 (Cook) Well No. 2541  
Office Address P. O. Box 1797, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) TA Gas Well  
Date well completed November 23, 1960  
Application for plugging filed November 19, 1964  
Application for plugging approved November 20 1964  
Plugging commenced November 20 1964  
Plugging completed November 20 1964  
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production None 19    
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2380 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Cimarron</u>			<u>1856</u>	<u>7 5/8"</u>	<u>312</u>	<u>None</u>
<u>Winfield</u>		<u>2356'</u>		<u>4.5</u>	<u>2380'</u>	<u>4'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sargents Casing Pulling rigged up and put 20 sks common cement over perf @ 2362' KDB. Stopped plug @ 2150' KDB. Then used 10 sks common from 350' back to 250'. Then used 5 sks common from 50' back to 0'. Complete on 11-20-64. Fox Welding cut off pipe 4' below ground & installed plateover csg. Then covered up same.

1-26-65  
**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 26 1965  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargents Casing Pulling Service  
Address 121 West 9th Street, Liberal, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
James A. Townsend (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James A. Townsend  
P. O. Box 1797, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 1965

My commission expires February 12, 1968 Lunice Rose Notary Public.



LEASE: ROBERT COOK #1-25  
OPERATOR: HAMILTON BROTHERS, INC.  
CONTRACTOR: EARL F. WAKEFIELD  
COMM: 11/19/60 COMP: 11/24/60

LOCATION: C NW/4  
SECTION 25/24-41W  
HAMILTON COUNTY, KANSAS  
CASING: 7 5/8" Set at 312'  
4 1/2" Set at 2380'

Shale and Shells	695
Red Bed and Shale	1340
Shale - Lime	1620
Shale and Lime	1850
Lime and Shale	2314
Lime	2380
T. D.	2380

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1964

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK) ss

I hereby certify that the above is a true and correct copy of the log on the Robert Cook #1-25 well, located C NW/4 Section 25, Township 24, Range 41 West, Hamilton County, Kansas.

EARL F. WAKEFIELD

By F. J. Basher

Subscribed and sworn before me this 7th day of December, 1960.

C. A. SNOW  
C. A. SNOW NOTARY PUBLIC

My commission expires July 26, 1962.

RECEIVED  
DEC 9 1964  
HAMILTON BROTHERS

HAMILTON BROTHERS

RECEIVED  
DEC 9 1960

12-10-60