


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Harvey County. Sec. 24 Twp. 22 Rge. (E) 2 (W)  
Location as "NE/CNW/SW" or footage from lines NW NE NW  
Lease Owner Musgrove Petroleum Corporation  
Lease Name ENVY Well No. 1  
Office Address 518 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed December 8, 1954  
Application for plugging filed verbally December 8, 1954  
Application for plugging approved verbally December 8, 1954  
Plugging commenced December 8, 1954  
Plugging completed December 8, 1954  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes, written 12-13-54

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3513' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	163'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 155'  
Set first plug at 155' with 15 sacks cement  
Filled hole with mud to 25'  
Set second plug at 25' with 5 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick  
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of December 19 54

My commission expires July 16, 1955.

Anna E. Raab  
Notary Public.

PLUGGING  
FILE SEC 24 T 22 R 2W  
BOOK PAGE 83 LINE 32

12-16-54

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	EWY #1
LOCATION:	NW NE NW Sec. 24-22-2W Harvey County, Kansas.
COMMENCED:	November 26, 1954
COMPLETED:	December 8, 1954

0	25	Surface soil
40	140	Sand & clay
140	163	Blue shale
163	325	Blue shale & shells
325	563	Lime & shale
563	610	Anhydrite
610	2944	Shale & lime
2944	2963	Shale
2963	2969	Miss. lime & shale
2969	3160	Lime, shale & chert
3160	3199	Lime & chert
3199	3265	Lime, shale & chert
3265	3275	Lime & chert
3275	3328	Lime, shale & chert
3328	3396	Shale & sandy lime
3396	3482	Shale & lime
3482	3510	Sandy shale
3510	3513	Shale & lime
	3513	Rotary Total Depth

Set 8-5/8" surface casing at 163' with 125 sacks cement & 2 sacks calcium chloride.

Dry and Abandoned.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, Gordon L. Koelling, do hereby certify that the above and foregoing is a true and correct copy of the log of the EWY #1, NW NE NW Section 24-22-2W, Harvey County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of December, 1954.

Armed E. Rame  
Notary Public

My commission expires July 16, 1955.

**PLUGGING**  
FILE SEC 24-22-2W  
BOOK PAGE 13 LINE 32