


15-009-15043-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 29 Twp. 16 Rge. 11 (E) (W)
Location as "NE/CNW/SW" or footage from lines c NE SE
Lease Owner Morgenstern & Specter
Lease Name Wendtlandt Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 5-20-43 19__
Application for plugging filed Nov. 21, 1963 19__
Application for plugging approved Nov. 22, 1963 19__
Plugging commenced November, 22, 1963 19__
Plugging completed November, 30, 1963 19__
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan Russell, Kansas
Producing formation Arbuckle Depth to top 3342 Bottom 3348 Total Depth of Well 3348 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	276 ft.	none
				5 1/2" CD	3333	2811 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3000-feet, dumped 5- sacks cement.
Circulated Mud at 310-feet, pumped 25- sacks cement at 280- feet.
Set a Rock Bridge at 25- feet, dumped 15- sack cement.

*Recd
11-22-63*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING COMPANY NO. 457
Address Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December 19 63

My commission expires Dec 1, 1964
Elsie Crady Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

COPY

BLACK & MARSHALL
J.L. Wendlandt No. 1.

SEC. 29 T. 16 R. 11W
ONE SE

Total Depth. 3348 $\frac{1}{2}$ '
Comm. 5-1-43 Comp. 5-20-43
Suct cr Treated.
Contractor. Geo. H. Hannum, Inc.
Issued. 11-20-43

County. Barton



CASING:
10 $\frac{3}{4}$ " 276' Com.
5 $\frac{1}{2}$ " 3333' Com. (ground measure)

Elevation.

Production. Pot. 136 B.

Figures Indicate Bottom of Formations.

shale & shells	257
sand	265
shale & shells	465
sand hd & sharp	525
Dakota shale	760
anhydrite	795
shale & shells	1275
salt	1425
shale & shells	1640
lime	1695
shale & shells	1800
lime	1855
lime & shale brks	1900
lime hd	1955
lime & shale brks	1995
shale	2010
shale & shells	2360
sand	2380
shale	2430
shale & shells	2530
lime brkn	2560
shale	2580
shale & shells	2880
lime	3339
sand	3341
lime	3348 $\frac{1}{2}$
Total Depth.	

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1963

CONSERVATION DIVISION
Wichita, Kansas

Tops: K. C. Lime (DFM) 3064
cored 3156-71
(full recovery)
cemented 5 $\frac{1}{2}$ " csg 2'
off btm, or 3333'
ground measure-60
sx cement
Arbuckle 3342