

15-009-03137-00-06

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Joseph #12

WELL NUMBER _____

SPOT LOCATION C NW SE SW

SEC. 29 TWP. 16 SRGE. 11 W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 8/16/85

Plugging Completed 8/21/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gulf Oil & Exploration & Production Co.

ADDRESS Box 1635, Houston, Tx. 77001

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3343'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	773'	none
				5 1/2"	3337'	759.65'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Gulf plugged bottom with 50 sacks cement. Could not get past 760'. Shot pipe at 760'. Hooked on to 5 1/2" & circulated 300 sacks cement up to 8 5/8. Pulled 24 joints of pipe.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. **RECEIVED**
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or **SEP 19 1985**
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and CONSERVATION DIVISION
the log of the above-described well as filed that the same are true and Wichita, Kansas
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1985

My Commission expires: _____



Irene Hoover
Notary Public

WELL LOG

COMPANY Gulf Oil Corporation

SEC. 29 T. 16S R. 11W

FARM Joseph

NO. 12

LOC. NW $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$

TOTAL DEPTH 3339'

COMM. 12-5-58


COMP. 12-12-58

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

COUNTY Barton
KANSAS



ELEVATION 1915 KB

PRODUCTION

CASING

20 \times 8-5/8" - 773' W/400 SXS
 15 \times 5 1/2" - 3337' W/100 SXS
 12
 13

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 70 Sub Soil & Post Rock
 70 - 100 Sand
 100 - 755 Shale
 755 - 783 Anhydrite
 783 - 1000 Red Bed & Shale
 1000 - 1585 Shale & Shells
 1585 - 1830 Shale & Lime Streaks
 1830 - 2220 Lime & Shale
 2220 - 2505 Shale & Lime Streaks
 2505 - 3120 Lime & Shale
 3120 - 3235 Lime
 3235 - 3336 Lime & Shale
 3336 - 3339 Arbuckle
 3339 - Total Depth - drlr's
 3343 = RTD

Geologic Tops

Heebner 2954'
 Toronto 2970'
 Douglas Shale 2986'
 Douglas Sand 3002'
 Brown Lime 3050'
 Lansing 3070'
 P B C 3317'
 Arbuckle 3334'

State of Kansas }
 County of Sedgwick } ss:

William J. Duckett of the Lewis Drilling Company

the above and foregoing is a true and correct copy of the log of the Joseph #12 well.

RECEIVED
 CORPORATION COMMISSION

William J. Duckett

PR 18 1935

before me this 17th day of December 1958

REGISTRATION DIVISION
 Wichita, Kansas Expires: August 20, 1960

A. R. Derrington
 (A. R. Derrington) NOTARY PUBLIC