

15-009-03136-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER D&C 10/23/57

LEASE NAME Joseph

WELL NUMBER 11

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 19 TWP. 16S RGE. 11 (X) or (W)

COUNTY Barton

Date Well Completed 10/23/57

Plugging Commenced 06/18/85

Plugging Completed 09/05/85

LEASE OPERATOR CHEVRON U.S.A. INC

ADDRESS P. O. BOX 12116, OKLAHOMA CITY, OK 73157

PHONE# (405) 949-7000 OPERATORS LICENSE NO. 4519

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? No record If not, is well log attached? Yes

Producing Formation Douglas Sand Shawnee LS Depth to Top 2996' 2992' Bottom 3008' 2939' T.D. 3090'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shawnee LS	Oil	2992	2939	8 5/8"	767	
Douglas Sd	Oil	2996	3008	5 1/2"	3090	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

OVER

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shirer Well Servicing Company License No. 522

Address P. O. Box 118 Hoisington, KS 67554

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

YVONNE MITCHELL

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Yvonne Mitchell

P. O. Box 12116

(Address) Oklahoma City, OK 73157

10-15-85

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 85

Mary Collier
Notary Public

My Commission Expires: April 20, 1985

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1985
CONSERVATION DIVISION
Wichita, Kansas

MIRU DDP. POH w/rods & tbg. MI 2 7/8" WS. RIH w/tbg to 3025'. MI Howco. Circ well w/ 6 bbls 9 ppg mud. Spot 50 sx Cl "A" cmt fr 3025' - 2600'. POH w/tbg. RD Howco. Circ 90 sx Cl "A" cmt to surface. Tie onto 8 5/8" x 5 1/2" annulus. Pmp 50 sx Cl "A" cmt @ 4 BPM. SIP=500 psi. 190 sx in top plug. State man Gib Scheck on location. Cap well, ID well, restore location. Well P&A'd 9-5-85. Not last well on lease. FINAL REPORT DROP

WELL LOG

COMPANY Gulf Oil Corporation

SEC. 29 T. 16S R. 11W
LOC. C/NE $\frac{1}{2}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$

FARM Joseph

NO. 11

TOTAL DEPTH 3090

COMML-16-57


COMP. 10-23-57

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

COUNTY Barton
KANSAS



ELEVATION 1912-K.B.

CASING

20	X	
15	X	8 5/8" - 767' w/375 SXS
12	X	
13	X	5 1/2" - 3090' w/75 SXS

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-540	Shale & sand
540-625	Shale & Red beds
625-680	Sand & Shale
680-757	Red beds
757-780	Anhydrite
780-900	Red beds
900-1870	Shale & shells
1870-3090	Shale & Lime
3090	Total Depth

Geologic Tops

Howard	2621
Topoka	2698
Heebner	2946
Toronto	2964
Douglas	2975
Lansing	3062

PBTD = 3053'

State of Kansas

County of Sedgwick

ss:

I, J. Fred Hambright

of the

Lewis Drilling

Company

upon which the above and foregoing is a true and correct copy of the log of the Joseph #11 well.

Subscribed and sworn to before me this 31st day of October 1957

My Commission Expires: 8-20-60

A. R. Derrington
(A. R. Derrington) PUBLIC