

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER D & C 02/28/51

LEASE NAME Joseph

WELL NUMBER 7

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 29 TWP. 16S RGE. 11 ~~OR~~ (W)

COUNTY Barton

Date Well Completed 02/28/51

Plugging Commenced 06/19/85

Plugging Completed 09/06/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CHEVRON U.S.A INC.

ADDRESS P. O. BOX 12116 OKLAHOMA CITY, OK 73157

PHONE# (405) 949-7000 OPERATORS LICENSE NO. 4519

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? No record If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3317' Bottom 3320' T.D. 3320'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3317	3320	8 5/8"	746'	
				5 1/2"	3317'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

OVER

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Super Oilwell Service License No. 6535

Address P. O. Box 534 Russell, KS 67665

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

YVONNE MITCHELL

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Yvonne Mitchell

(Address) P. O. Box 12116 Oklahoma City, OK 73157

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1985

My Commission Expires: April 20, 1986
Mary Cahlania Notary Public

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1985
CONSERVATION DIVISION
Wichita, Kansas

10-15-85

MI 2 7/8" WS. MIRU Kincade DDP. RIH w/tbg to 3272'. Circ well w/60 bbls, 9 ppg mud. Spot 50 sx Cl "A" cmt fr 3272' - 2842'. RDMO Howco. POH w/tbg. RDMO PU MI SOS WSU. RIH w/tbg to 611'. MI Howco. Circ 70 sx Cl "A" cmt to sfc. POH w/tbg. Tie onto 8 5/8" x 5 1/2" annulus. Pmp 130 sx Cl "A" cmt on vac. Total 200 sx cmt in top plug. Cmt csg off 6' below GL. Top off csg w/2 yards redimix. Weld cap, ID well. Well P&A'd 9-6-85. State man Gib Scheck on location. Not last well on lease. FINAL REPORT DROP

WELL NO. 7 LEASE Joseph COMPANY Gulf Oil Corporation A.F.E. 2548

DATE—DRILLING BEGAN 2-6-51 WELL COMPLETED 2-28-51 FIRST PRODUCTION 2-26-51

SAND RECORD Top Arbuckle 3316' TOTAL DEPTH 3320'

INITIAL PRODUCTION OIL: "P" 79 Barrels
WATER: None

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	BACKS CEMENT	LBS. CAL. CNLO.	PULLED	LEFT IN
8-5/8"	32	8V	C	Smls.	746'	345			746'
5-1/2"	14	8R	*	Smls.	3317'	100			3317'
*47 Jts.			Class A						
60 Jts.			Class B						

S— 29 T— 16S R— 11W

			C-		
			NW		
			NE		
			SW		
			Barton		
			County		
			Kansas		

ELEVATION— 1892'

DISTANCE H: Top collar on 5-1/2" casing to rotary bushing is 6'.

ACIDIZED: With 500 gallons 2-27-51

ACIDIZED: 5-1-53 to 5-4-53

ACIDIZED: with 500 gallons

PRODUCTION: Before "P" 9 oil 75 water

After "P" 29 oil 261 water 5-9-53

A.F.E. 3139

WELL LOG ON JOSEPH #7

Spudding date: 2/6/51
 Date casing set: 2/17/51
 Date rotary completed: 2/15/51
 Date cable completed:

Location:
 Center NW 1/4 SW Sec. 29-160-11W
 Barton County, Kansas

FROM	TO	FORMATION	REMARKS
0	215	Surface soil and shale	
215	1165	Shale and shales	Ran 27 jts. 8-5/8" csg. at 610' w/375 sz. bulk cement
1165	1835	Shale and lime	
1835	1955	Lime	
1955	2160	Shale and shales	
2160	2690	Shale and lime	
2690	2755	Lime	
2755	2800	Lime and shale	
2800	2905	Lime	
2905	2960	Lime and shale	
2960	3320	Lime	
3320		TOTAL DEPTH	Ran 107 jts. 5 1/4" O. D. 8 thread csg. at 3317' w/100 sz. bulk cement.

Subscribed and sworn to before me this 21st
 day of February, 1951

I certify the above and foregoing to be a true and exact
 copy of the original driller's log on the Joseph #7

Elmer Stargen
 Notary Public
 My commission expires:
 My commission expires Aug. 28, 1951

HERNDON DRILLING COMPANY
C. J. Moore
 By:
 Title: