

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Locate well correctly on above
Section Plat

Pawnee County, Sec. 25 Twp. 22 Rge. 16 (E) X (W)
 Location as "NE/CNW/SW" or footage from lines NW NW SW
 Lease Owner Little George Oil Co.
 Lease Name Doll "A" Well No. 1
 Office Address 225 Sutton Place - Wichita, Ks. 67202
 Character of Well (completed as Oil, Gas or Dry Hole) Gas
 Date well completed 11-28-72 19
 Application for plugging filed 4-29-74 19
 Application for plugging approved 4-20-74 19
 Plugging commenced 19
 Plugging completed 5-15-74 19
 Reason for abandonment of well or producing formation Well wouldn't pay to produce.
 If a producing well is abandoned, date of last production April 1974 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4055 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug w/45 sx. Plugged from 4055 back to 3600. Used 100 sx cement, 200 Gel, 3 hulls. Cemented surface from top to bottom. Recovered 2010' 4 1/2" -- 200' 8 5/8."

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 17 1974
 CONSERVATION DIVISION
 Wichita, Kansas


6-17-74

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor F & F Well Serv.
 Address Box 37 Towanda, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss. Ronald S. Schraeder

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ronald S. Schraeder
 225 Sutton Place - Wichita, Kansas (Address)



SUBSCRIBED AND SWORN TO before me this 14th day of June 1974

My commission expires March 1, 1978

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-145-20274-0000

COMPANY Hershberger Explorations, Inc.

SEC. 25 T. 22S R. 16W
 LOC. NW NW SW

FARM Doll "A" NO. 1

TOTAL DEPTH 4,055'
 COMM. November 18, 1972

COMP. November 28, 1972

SHOT OR TREATED
 CONTRACTOR H-30, Inc.

ISSUED

20
 15
 12
 13

10
 8-5/8"
 6
 5

271' cemented w/225 sxs cement ELEVATION 2,011 KB

4 1/2" 4,054' cemented w/100 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Clay	105'
Sand	185'
Shale and Hard Sand	273'
Shale and Sand	455'
Sand	515'
Red Bed and Shale	982'
Anhydrite	1,005'
Shale	1,340'
Shale and Shells	1,810'
Shale and Lime	1,965'
Lime and Shale	2,635'
Shale and Lime	3,090'
Lime and Shale	3,625'
Lime	3,875'
Lime and Chert	3,970'
Lime, Shale and Chert	4,019'
Lime and Chert	4,055'
Rotary Total Depth	4,055'

PRODUCTION

Date 12-5
 COUNTY Pawnee
 L.E.L. _____ KANSAS
 W.A.S. _____
 B.P. _____
 M.M. _____
 M.S. _____
 ACCTG. _____

RECEIVED
 STATE CORPORATION COMMISSION
 APR 30 1974
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting

 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 4th. day of December, 1972.

WILLIS O