

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pawnee County, Sec. 10 Twp. 22S Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines C E/2 SE

Lease Owner ALPINE DRILLING CO., INC.

Lease Name Lewis "A" Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 17 1971

Application for plugging filed December 7 1972

Application for plugging approved December 8 1972


Plugging commenced December 15 1972

Plugging completed December 19 1972

Reason for abandonment of well or producing formation Non-productive in commercial quantities

If a producing well is abandoned, date of last production May 1972

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4075 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1054'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 4004' to 3880'.
Run 5 sacks of cement from 3880' to 3850'. Set plug at 315'. Filled with rock from 315' to 300'. Run 5 yards of ready mix cement from 300' to base of cellar.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 East Sixth, Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]

800 Bitting Building, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 18th day of January, 1973

My commission expires February 23, 1976

Patricia J. Phillips Notary Public.



GABBERT JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

LEWIS "A" #1
 C E/2 SE/4, Sec. 10-228-17W
 Pawnee County, Kansas

Commenced: April 6, 1971
 Completed: April 17, 1971

OPERATOR: Alpine Drilling Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	50	Sand	Ran 26 joints of 28# used 8 5/8" Casing, set @ 1034' w/400 sacks PD @ 3:45 PM 4/7/71. Cement Circ.
50	130	Shale and Sand	
130	470	Shale	
470	580	Sand	
580	565	Shale and Redbed	
565	1045	Redbed	
1045	1068	Anhydrite	
1068	1825	Redbed and Shale	
1825	2185	Shale and Lime	
2185	2395	Lime	
2395	2810	Lime and Shale	
2810	3010	Shale and Lime	
3010	3615	Lime and Shale	
3615	3920	Lime	
3920	3990	Lime and Shale	Ran 128 joints of used 5 1/2" Casing Set @ 4073' w/150 sacks 60/40 Pozmix 18% Salt. PD @ 12:45 AM 4/17/71
3990	4018	Lime	
4018	4055	Lime and Sand	
4055	4075	Lime	
4075	TD		

RECEIVED
 STATE CORPORATION COMMISSION
 APR 15 1973
 CONSERVATION DIVISION
 Wichita, Kansas

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C-E/2 SE/4 Section 10-228-17W, Pawnee County, Kansas, to the best of my knowledge and belief.

James S. Sutton II
 James S. Sutton II

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 20th day of April 1971, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton
 Barbara J. Layton, Notary Public

My commission expires February 1, 1972

