

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-21,168-0000

LEASE NAME Sowers

WELL NUMBER 1

SPOT LOCATION C NE SW SW

SEC. 24 TWP 22 RGE J8 (E) or (W)

COUNTY Pawnee

Date Well Completed 10-24-84

Plugging Commenced 10-25-84

Plugging Completed 10-25-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market - Suite 1110, Wichita, Kansas 67202

PHONE # (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4375

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged well with 120 sxs 60/40 poz, 2% gel, 3% cc as follows: 1150'-50 sxs; 480'-40 sxs; 40'-10 sxs with plug; rathole-10 sxs; mousehole-10 sxs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

11-8-84


STATE OF Kansas COUNTY OF Pratt, ss. STATE CORPORATION COMMISSION

Arnie Little (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little  
(Address) P. O. Box 329, Pratt, Kansas 67124

NOV 08 1984

CONSERVATION DIVISION  
Wichita, Kansas



SUBSCRIBED AND SWORN TO before me this 6 day of November, 1984

Mary L. Tjaden  
Notary Public

My Commission expires: 3/22/88



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

**Oilfield Services, Inc.**

DRILLER'S WELL LOG

Sowers #1  
 C NE SW SW Sec. 24-22S-18W  
 Pawnee County, Kansas  
 Commenced: 10-15-84  
 Completed: 10-25-84  
 API #15-145-21,168  
 Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	798	Sand, Red Bed	Ran 11 joints (455') new, 24#, 8 5/8" surface casing. Set at 465' with 200 sxs Lite, 6% gel, 3% cc 75 sxs Common, 3%cc. Job by Buie. Cement did circulate. Plug down at 4:45 a.m. on October 16, 1984.
798	1506	Red Bed	
1506	2450	Shale	
2450	4375	Lime, Shale T.D.	

RTD 4375'

Plugged well with 120 sxs 60/40 poz, 2% gel, 3% cc as follows: 1150'-50 sxs; 480'-40 sxs; 40'-10 sxs with plug; rathole-10 sxs; mousehole-10 sxs. Job by Buie. Complete at 9 a.m. on October 25, 1984. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 \_\_\_\_\_  
 ARNIE LITTLE, VICE-PRESIDENT



*Mary L. Tjaden*  
 \_\_\_\_\_  
 NOTARY PUBLIC

My Commission Expires:

3/22/88

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 08 1984

CONSERVATION DIVISION  
 Wichita, Kansas