

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pintail Petroleum Ltd.

ADDRESS 225 N. Market, Suite 300 Wichita, KS 67202

PHONE# (316) 263-2243 OPERATORS LICENSE NO. 5086

Date Well Completed

Character of Well Oil

Plugging Commenced 10-11-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-11-93

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4290'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	297'	none
				4 1/2	4289'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Pumped 150# hulls, 50 sks cement w/150# hulls, 20 sks gel, 65 sks cement down 4 1/2" casing.
Shut in. 60/40 pos, 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No.

Address P. O. BOX 347 CHASE, KS. 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum Ltd.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of November, 19 93

James S. Sierberg
Notary Public

My Commission Expires:



STATE: KANSAS 1-1-29 MAP NO. _____ S-T-R 24-22S-18W WD
 OPER BROUCHER OIL INC SPOT W/2 W/2 NW INIT
BOX 1367, GREAT BEND, KS CO PAWNEE WDD
 WELL 3 GEORGE S BLACKWELL ELEV 2070 KB FIN
 CONTR WOODMAN & LANNITTI
 FIELD EDDY (LAN-B/PENN)
 IP OIL WELL (FORM & INTVL UNKNOWN)



API 15-145-20180 ••••• TEMP COMP
 SPUD 10-25-77, 8 5/8" @ 297 w/225, Geol Frank Hamlin
 RTD 4290, 4 1/2" @ 4288 w/150
OIL WELL, FORMATION & INTERVAL UNKNOWN
TEMPORARILY COMPLETED 12-19-77

KINDERHOOK SD 4225 - 2155
 WEATHERED VIOLA 4247 - 2177
 VIOLA 4269 - 2199
 LTD 4289 - 2219
 RTD 4290 - 2220
 TD IN VIOLA

COMP ISSUED 1-3-78

KB LOG TOPS: ¹¹¹¹ 1120 - 1977
 HEEBNER 3606 - 1536
 TORONTO 3623 - 1553
 DOUGLAS 3632 - 1562
 BROWN LM 3700 - 1630
 LANSING 3709 - 1639
 B/KANSAS CITY 3997 - 1927
 FORT SCOTT 4092 - 2022
 CHEROKEE ✓ 4109 - 2039
 PENN CONGL 4155 - 2085
 MISS ✓ 4172 - 2102
 KINDERHOOK 4220 - 2150
 (CON'T FOR TOPS)

 Petroleum Information
 CORPORATION
 Copyrighted 1977, Reproduction Prohibited

Blackwell 3

15-145-20480-0000

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30

API #

15-145-20480

Surface 297' 85/8"

Cement ~~5289' 4 1/2"~~

28524

Long string 150.04
4289' 4 1/2"

squeezed to surface
plug down 4 1/2"

Cement 150.04

Perforations

4172 - 4910

P.B.T.D.

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1993
CONSERVATION DIVISION
Wichita, Kansas