

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
May or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Pawnee County. Sec. 24 Twp. 22S Rge. 18W XXXXXX
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Continental Oil Company
Lease Name H. M. Wonn Well No. 1
Office Address Box 161, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-17 19 59
Application for plugging filed 10-23 19 59
Application for plugging approved 10-26 19 59
Plugging commenced 10-29 19 59
Plugging completed 11-7 19 59
Reason for abandonment of well or producing formation No commercial zones encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank BroadfootProducing formation none Depth to top Bottom Total Depth of Well 4445 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	oil	4212	4218	8 5/8"	867	none
Basal Penn.	oil & water	4161	4168	4 1/2"	4272	3602
Lansing KC	water	3920	3928			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand to 3910'.

Dumped 5 sacks of cement to 3850'.

Pumped 20 sacks of acquagel and 80 sacks of Portland cement plugging hole to surface.

11-19-59

RECEIVED
STATE OF KANSAS
COMMISSION
NOV 19 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

F. L. Dunn, employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC

11-16-59

State DWM IWS File

(Signature)

F. L. Dunn
District SuperintendentBox 161, Great Bend, Kansas
(Address)SUBSCRIBED AND SWORN to before me this 16th day of November, 19 59My commission expires August 1, 1960

Notary Public.