

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 3 TWP. 22 RGE. 15W E/W
Location as in quarters or footage from lines:
S/2 NE NE

Locate Well
correctly on above
Section Platt.

Lease Owner A: Scott Ritchie
Lease Name Compton #4 Well No. _____
Office Address 125 N. Market Suite 950 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-27-82
Plugging completed 9-1-82
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 3940'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	594'	none
				5-1/2"	3937'	3173'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3900' and ran 5 sacks cement. Shot casing @3197',
pulled a total of 101 joints of 5-1/2" casing. Plugged well with 3 sacks hulls,
10 sacks gel, 70 sacks cement, 1 sacks hulls, 10 sacks gel, released plug and
displaced with 80 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Mike Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 82

My Commission expires:



[Signature]
Notary Public.
STATE CORPORATION COMMISSION

SEP 09 1982

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: December 3, 1974
DATE COMPLETED: December 11, 1974

A. Scott Ritchie
COMPTON # 4
C S/2 NE/4 NE/4
Sec. 3-T22-R15W
Pawnee County, Kansas

0 - 110' Surface Soil and Sand
110 - 140' Clay
140 - 460' Sand, Clay
460 - 925' Red Bed
925 - 948' Anhydrite
948 - 990' Red Bed, Shale
990 - 1800' Shale and Shells
1800 - 3388' Lime, Shale
3388 - 3393' Shale
3393 - 3421' Lime and Shale
3421 - 3498' Shale
3498 - 3508' Lime and Shale
3508 - 3736' Lime
3736 - 3937' Lime, Shale, Chert, Sand
3937 - 3940' Dolomite
3940' RTD

ELEVATION: 1977 K.B.

FORMATION TOPS

Anhydrite 925
Heebner 3388
Douglas 3421
Brown Lime 3498
Kansas City 3508
Base K.C. 3736
Viola 3845
Simpson 3878
Arbuckle 3937
RTD 3940

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1982
CONSERVATION DIVISION
Wichita Kansas

SURFACE PIPE: Set used 8 5/8" pipe, 28#, @ 594' w/200 sacks 60/40 pozmix, 2% gel, 3% cc and 150 sacks Common, 2% gel, 3% cc.

PRODUCTION PIPE: Set used 5 1/2" pipe, 14 1/2# at 3938' w/100 sacks 60/40 pozmix w/10 bbls salt flush ahead of plug.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 13th day of December, 1974

Deborah M. Hague
Notary Public

My Commission Expires: April 11, 1978