

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 3 Twp. 22 Rge. 15 ~~E~~/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW NE SE

Lease Owner Wm. D. Witcraft

Lease Name Compton Well No. 1

Office Address Box 811 - Great Bend, Ks. 67530

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 2-1- 1978

Application for plugging filed 2-1 1978

Application for plugging approved 2-1 1978

Plugging commenced 2-1 1978

Plugging completed 2-1 1978

Reason for abandonment of well or producing formation


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3961

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 600', plug with 50 sks. 50/50 pozmix, 2% Gel thru drill pipe.

Mud to 240' - plug and 25 sks. cement thru drill pipe.

Mud to 40', $\frac{1}{2}$ sk. hulls, plug and 10 sks. cement

2 sks. rat hole

RECEIVED
STATE CORPORATION COMMISSION

FEB 07 1978

2-7-78

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Larry Curtis (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis

Box 823 - Great Bend, Ks. 67530

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1978

Notary Public, Dorothy M. Hague

My commission expires 4-11-78

DRILLERS' WELL LOG

DATE COMMENCED: January 25, 1978
DATE COMPLETED: February 1, 1978

Wm. D. Witecraft
COMPTON #1
SW NE SE Sec 3-T22S-R15W
Pawnee County, Kansas

ELEVATION: 1981 K.B.

0 - 120'	Gley & Sand
120 - 160'	Sand & Shale
160 - 250'	Sand
250 - 395'	Shale
395 - 485'	Sand
485 - 570'	Red Bed
570 - 939'	Shale
939 - 973'	Anhydrite
973 - 2197'	Shale
2197 - 3022'	Shale & Lime
3022' - 3398'	Lime
3398' - 3402'	Shale
3402 - 3510'	Shale & Lime
3510' - 3518'	Lime & Shale
3518 - 3755'	Lime
3755 - 3863'	Lime, Shale
3863 - 3893'	Chert
3893 - 3920'	Shale
3920 - 3934'	Sand
3934 - 3957'	Shale, Lime
3957 - 3961'	Dolomite
3961'	RTD

FORMATION TOPS

ANHYDRITE	939
TOPEKA	3022
HEBENER	3398
BR. LIME	3510
LANSING	3518
BASE K.O.	3755
VIOLA	3863
SIMPSON SH.	3893
SIMPSON SD.	3920
ARBUCKLE	3957
RTD	3961

Surface Pipe: Set Used 8-5/8" pipe at 570' with 300 sacks 50/50 pozmix, 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 6th day of April 1978.

Dorothy M. Hogue
Notary Public

My Commission Expires: April 11, 1978

RECEIVED
STATE CORPORATION COMMISSION
FEB 07 1978
CONSERVATION DIVISION
Wichita, Kansas