

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

PAWNEE CO, KANSAS County. Sec. 1 Twp. 22S Rge. 15W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner K & E DRILLING, INC.
Lease Name MacDONNELL Well No. 1
Office Address 719 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed June 6th, 1959 19
Application for plugging filed June 6th, 1959 19
Application for plugging approved June 6th, 1959 19
Plugging commenced June 6th, 1959 19
Plugging completed June 6th, 1959 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3897 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	356'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 300' set plug
with 1/2 sx hulls and 20 sx cement. Filled
with heavy mud to 35' set solid bridge with
1/2 sx hulls and 10 sx cement to base of
cellar. Job complete 6-6-59

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
DALE SILCOTT (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott, of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1959

My commission expires August 11th, 1962.

Patricia M. Edwards, Notary Public.

PLUGGING
FILE SEC 1 T 22 R 15
BOOK PAGE 45 LINE 13

15-145.00110-0000

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center
Wichita 2, Kansas

WELL NAME: #1 MacDONNELL
LOCATION: SE NW SE
Sec. 1-22S-15W
PAWNEE CO, KANSAS

CONTRACTOR: K & E DRILLING, INC.
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: May 27th, 1959

CASING RECORD: 8-5/8" @ 356' (275 sx cmt)

COMPLETED: June 6th, 1959

ROTARY TOTAL DEPTH: 3897'

ELEVATION: 1965' KB

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Sand	245
Shale & Shells	356
Sand & Shale	880
Anhydrite	905
Shale	1550
Salt	1685
Shale & Lime	1840
Lime & Shale	2085
Lime	2410
Lime & Shale	2885
Shale & Lime	3055
Shale	3115
Lime	3677
Lime & Shale	3770
Shale	3790
Viola Lime	3842
Shale & Cherty Lime	3881
Lime	3897

R.T.D. 3897

RECEIVED
STATE OF KANSAS COMMISSION

JUN 10 1959

CONSERVATION DIVISION
Wichita

CERTIFICATION

State of KANSAS
County of SEDGWICK ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state
that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott

Subscribed and sworn to before me this 8th day of June, 19 59

My Commission expires: August 11th, 1962

Patricia M. Edwards, Notary Public

PLUGGING	
FILE	SEC 122 R15H
BOOK	45-11-10

K & E DRILLING, INC.



Rotary Drilling Contractors