

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-20,808,0001

LEASE NAME BURMEISTER "B"

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 27 TWP. 16 RGE. 11 (E or W)

LEASE OPERATOR Sid TOMLINSON

ADDRESS 1802 WILLOWOOD DR, STILLWATER, OK 74075 COUNTY BARTON

PHONE#(405) 372-2833 OPERATORS LICENSE NO. 6412

Date Well Completed 12-13-74

Character of Well SWD

Plugging Commenced 1-29-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-29-92

The plugging proposal was approved on 1-28-92 (date)

by SCHECK and Deines (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? N/A

Producing Formation SWD Depth to Top N/A Bottom N/A T.D. 3580

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>LANSING</u>	<u>WATER</u>	<u>3092</u>	<u>3326</u>	<u>8 5/8</u>	<u>368'</u>	<u>-0-</u>
<u>ARBUCKLE</u>	<u>WATER</u>	<u>3393</u>	<u>3580</u>	<u>5 1/2</u>	<u>3483</u>	<u>-0- * Squeezed</u>
						<u>HOLE @ 2324'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

* Hole in 5 1/2 previously squeezed w/ 250 SX TO 1000 PSI, ALSO SQUEEZED 5 1/2 X 8 5/8 ANNULUS w/ 250 SX (Jan. 1984). PRESSURED BACKSIDE TO 800#. PUMPED DOWN 5 1/2 CASING w/ 325 SX 60/40 POZ, 8% GEL, 500# COTTONSEED HULLS. MAX 900# PRESSURE SHUT IN 400#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING Co. License No. _____

Address BOX 31, RUSSELL KS, 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sid TOMLINSON RECEIVED

STATE OF OKLA. COUNTY OF PAYNE, ss. 02-24-92

Sid TOMLINSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sid Tomlinson

(Address) 1802 WILLOWOOD DR, STILLWATER OK.

SUBSCRIBED AND SWORN TO before me this 19 day of Feb, 19 92

Jelen A Cole
Notary Public

My Commission Expires: 5-24-92

JAN 28 1992

DRILLERS LOG

No. 2 Burmeister "B"

CASING RECORD:

3-5/8" @ 368'
w/250 sx cmt

5-1/2" @ 3478'
w/125 sx cmt

TOTAL DEPTH: 3580'

COMPANY: Mr. J.S. (Sid) Tomlinson

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: May 31, 1974

COMPLETED: June 10, 1974

CONSERVATION DIVISION

WASHITAING:

E/2 SE SW
27-16S-11W
Barton County,
Kansas

ELEVATION:

FORMATION	FROM	TO	REMARKS
Clay, Sand & Shale	0	350	
Shale	350	757	
Anhydrite	757	785	
Shale & Shells	785	1290	
Shale & Lime	1290	1630	
Lime & Shale	1630	1843	
Shale & Lime	1843	2728	
Lime & Shale	2728	3075	
Lime	3075	3123	
Lime & Shale	3123	3190	
Lime	3190	3430	
Lime, Arbuckle	3430	3475	
Lime	3475	3525	
Lime, Granite Wash	3525	3575	
Granite	3575	3580	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 13th day of June, 1974.

D. Ann Drennan
Notary Public

My Commission Expires:

December 28, 1977

