


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-009-30090-0090
WELL PLUGGING RECORD

Barton County, Sec. 27 Twp. 16 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines Gen NL SW NW
Lease Owner Hinkle Oil Co.
Lease Name Willenberg #6 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-17-59 19____
Plugging completed 3-23-59 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division, or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3375' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	122'	none
				5-1/2"	3375'	2727'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3363' and found it open.
Filled w/sand to 3085' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing, cleared hole and checked good mud to 270', set rock bridge to 260' and dumped 25 sacks of cement. Mudded the hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

APR 1 1959 04-01-59
STAI
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE ss.
I, Noel J. Knight (employee of owner) or (OWNER/OPERATOR) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of March, 19 59

9-27-62

Thomas V. Dwyer
Notary Public.

My commission expires _____

PLUGGING
FILE SEC. 27 T. 16 R. 11 W
BOOK PAGE 21 LINE 19

Willenberg No. 6, Cen. 11. SW NW 27-16-11W Barton Co. Kansas.

Owners: Hinkle Oil Co. & Gulf Oil Corporation

Contractor: J. B. Hinkle.

Commenced 4-29-47

Completed 5-9-47

Elevation 1925

Casing record.

8" 122'

5 1/2" 3375'

0	118	S urface
118	439	Shale and shells
439	495	Shale
495	518	Sand
518	750	Shale
750	770	Anhydrite
770	1175	S hale and shells
1175	1447	Shale and salt
1447	1605	lime and shale
1605	1790	Shale and shells
1790	1965	Shale and lime
1965	2100	Shale and shells
2100	2427	Shale
2427	2513	Shale and lime
2513	2752	Shale
2752	2787	Lime
2787	2933	Shale and lime
2933	2989	Lime
2989	3131	Lime & S hale
3131	3163	Lime
3163	3190	Lime very soft
3190	3194	Lime
3194	3240	S hale and Lime
3240	3375	Lime

Upper Lime Brown	3051
Lansing	3071
Conglomerate	3345
Artusicle	3370

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1959

CONSERVATION DIVISION
Wichita, K. C.

State of Kansas)
) SS
County of Sedgwick.)

J. B. Hinkle hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

J. B. Hinkle

Subscribed to and sworn to before me this 19th day of May, 1947.

W. P. H. Hinton
N. P.

My commission expires 1-17-50

PLUGGING
FILE SEC. 27 T. 16 R. 11W
BOOK PAGE 21 LINE 19

Willenberg No. 6, Cen. E. SW NW 27-16-11W Barton Co. Kansas.

Casing record.
8" 122'
5 1/2" 3375'

Owners: Hinkle Oil Co. & Gulf Oil Corporation
Contractor: J. B. Hinkle.
Commenced 4-29-47 Completed 5-9-47
Elevation 1925

0	118	Surface
118	439	Shale and shells
439	495	Shale
495	518	Sand
518	750	Shale
750	770	Anhydrite
770	1175	Shale and shells
1175	1447	Shale and salt
1447	1605	Lime and shale
1605	1790	Shale and shells
1790	1965	Shale and lime
1965	2100	Shale and shells
2100	2427	Shale
2427	2513	Shale and lime
2513	2752	Shale
2752	2787	Lime
2787	2933	Shale and lime
2933	2989	Lime
2989	3131	Lime & shale
3131	3163	Lime
3163	3190	Lime very soft
3190	3194	Lime
3194	3240	Shale and Lime
3240	3375	Lime

Wops:	Upper Lime Brown	3051
	Lansing	3071
	Conglomerate	3345
	Arbuckle	3370

STATE OF KANSAS
SEAL OF THE CONSERVATION COMMISSION

APR 1 1959

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
) SS
County of Sedgwick,)

J. B. Hinkle hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

J. B. Hinkle

I subscribed to and sworn to before me this 19th day of May, 1947.

Muriel A. Upton
N. P.

My commission expires 1-17-50

PLUGGING
FILE SEC. 27 T. 16 R. 11W
BOOK PAGE 21 LINE 19