

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,009-20,766 0000

LEASE NAME Burmeister "B"

WELL NUMBER 1

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 27 TWP. 16 RGE. 11 ~~XXXX~~ (W)

COUNTY Barton

Date Well Completed 3-7-74

Plugging Commenced 8-10-93

Plugging Completed 8-10-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR SID TOMLINSON

ADDRESS 1802 Wildwood Drive

PHONE# (405) 372-2833 OPERATORS LICENSE NO. 6412

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-9-93 (date)

by Dennis Hamel, Witnessed by Bruce Bayse (KCC District Agent's Name).

Is ACO-1 filled? YES If not, Is well log attached? _____

Producing Formation Arbuckle Depth to Top 3292 Bottom 3296 T.D.3405 PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Oil/water	2987	89	8 5/8	363	-0-
Lansing	Oil/water	3114	17	5 1/2	3424	-0-
Arbuckle	Oil/water	3392	96			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforated 5 1/2 csg w/4 shots @ 770' (Anhydrite), and 4 shots @ 1450' (Base of salt). Mixed 190 sx 60/40 Poz + 10% gel and pumped into 5 1/2 csg: 40 sx cmt with 400# cottonseed hulls, 8 sx gel spacer mixed 9#/gal, 150 sx cement. Waited 3 hours. Pumped 50 sx 60/40 Poz + 8% gal, squeezed to 550#. Pressured

(If additional description is necessary, use BACK of this form.)
backside to 500# - it was full.

Name of Plugging Contractor Sid Tomlinson License No. 6412

Address 1802 Wildwood Drive, Stillwater, OK 74075

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: SID TOMLINSON

STATE OF OK COUNTY OF PAYNE, ss.

SID TOMLINSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sid Tomlinson RECEIVED
STATE CORPORATION COMMISSION
(Address) 1802 Wildwood Dr. Stillwater, OK



SUBSCRIBED AND SWORN TO before me this 24th day of August, 1993
Helen A. Cole Notary Public
Wichita, Kansas

My Commission Expires: 5-24-96

Aug 27 1993
Form CP-4
Revised 05-88

KANSAS DRILLERS LOG


S. 27 T. 16 R. 11 W

API No. 15 — 009 — 20,766
 County Number

Loc: NW SE SW

County Barton

640 Acres
 N



Operator J. S. Tomlinson
 Address 1022 United Founders TWR
Oklahoma City, Oklahoma

Well No. #1 Lease Name Burmeister "B"

Footage Location SW/4
990 feet from (S) line 990 feet from (E) line

Principal Contractor Red Tiger Geologist J. E. Jespersen

Spud Date 12-12-73 Total Depth 3425' P.B.T.D. 3404'

Date Completed 3-30-74 Oil Purchaser PHILLIPS

Locate well correctly
 Elev. Cr. 1930

Dr. RB 1935

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in. O.D.)	Weight lbs/ft	Setting depth	Type cement	Sacks	Type and percent additives
<u>SURFACE</u>	<u>12 1/4</u>	<u>8 5/8</u>	<u>28#</u>	<u>363'</u>	<u>COMMON</u>	<u>200</u>	<u>2% GEL</u> <u>3% CA CI</u>
<u>PRODUCTION</u>	<u>7 7/8</u>	<u>5 1/2</u>	<u>14#</u>	<u>3424'</u>	<u>POZ</u>	<u>250</u>	<u>18% SALT</u>

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			<u>4</u>	<u>JETS</u>	<u>3392-96</u>

TUBING RECORD

Size	Setting depth	Packer set by
<u>2 7/8</u>	<u>3397'</u>	<u>NONE</u>

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production 3-7-74 Producing method (flowing, pumping, gas lift, etc.) PUMPING

RATE OF PRODUCTION PER 24 HOURS
 Oil 51 bbls/day Gas -0- MCF Water 10 bbls/day Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) ARBUCLE Producing interval (at) 3392-96

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, the completed copy of this Drillers Log shall be transmitted to the State Geological Survey at Kansas, 4130 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3950-BB, Meridian (P.O. Box 17027), Wichita, Kansas 67217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey at Kansas, Lawrence, Kansas 66044.

WICHITA KANSAS DIVISION
 C-10-1972

Operator **SID TOMLINSON** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWD, ETC. **OIL**

Well No. **1** Lease Name **BURMEISTER "B"**

S 27 T 16 R 11 W **C NW SE SW**

WELL LOG

Show all important zones of porosity and contents thereof; zones intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
---------------------------------------	-----	--------	------	-------

DRESSER ATLAS RAN GAMMA RAY/NEUTRON/WATERLOG ELECTRIC LOG TOPS:

ANHYDRITE	756
HEEBNER	2967
BRN LM.	3066
LANSING	3088
ARBUCKLE	3382
ARB. POROSITY	3392
T.O.	3425

DST #1 3090-3130 (LANSING A+B ZONES)

TOOL OPEN 1 HOUR W/ STANDING HEAD THEN OUT

Rec. 500' HYDRA-SW CUT MIL
725' HYDRA-SW OIL CUT MIL

FP 257#-452#
ISIP 569#/30" FSIP 569#/30"

DST #2 3382-3400 (ARBUCKLE)

TOOL OPEN 1 HOUR W/ STANDING HEAD THEN OUT

Rec 1590' HYDRA-SW OIL
1200' HYDRA-SW OIL CUT MIL

FP 66#-644#
ISIP 1034#/30" FSIP 1034#/30"

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Sid Tomlinson</i> Signature
	Operator
	4-12-74 Date

RECEIVED JUN 10 1975
WICHITA DIVISION
Wichita, Kansas