


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-009-15033-0000

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 27 Twp. 16 Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NE SE
Lease Owner Hinkle Oil Co.
Lease Name Frances Burmeister #3 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-19-57 19____
Plugging completed 9-24-57 19____
Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R.M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3385 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	98'	none
				5 1/2"	3383'	2785'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3385' and found it open.
Filled w/sand to 3370' and ran 5 sacks of cement. Pulled 68 jts. 5 1/2" casing, pumped 11 sacks gel mud into casing trying to get circulation. Pulled 2 jts 5 1/2". Pumped 22 sacks gel mud trying to get circulation. Pulled 8 jts 5 1/2". Pumped 15 sacks of gel mud into casing, got circulation, pulled 1 jt, circulated 5 1/2" w/100 sacks cement, pulled final 10 jts. Run bailer into hole to 135', baled off fluid. Mudded the hole to 25', set a 10' rock bridge to 15' and ran 5 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

_____(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
(Address) _____

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 57.

Thomas V. Daggis Notary Public.

My commission expires 9-27-58

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 - 1957
10-03-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 27 T. 16 R. 11W
BOOK PAGE 44 LINE 45

Casing record.
 8 5/8" 98'
 5 1/2" 2383

Burmeister 3 SE NE SE 27-16-11
 Hinkle and Franco Central Oil Company
 Contractor J. B. Hinkle.
 Elevation 1928
 Commenced 1-25-51 Completed 2-6-51

0	98	surface soil and shale
98	185	shale and shells
185	285	red bed and shale
285	360	sand
360	500	shale and sand
500	530	pyrite
530	650	shale and sand
650	775	shale and lime
775	980	shale and shells
980	1153	shale, shells and lime
1153	1400	shale and shells
1400	2470	shale and lime
2470	2600	sticky shale and lime
2600	2887	shale and lime
2887	2985	lime and shale
2985	3169	lime
3169	3245	lime and shale
3245	3305	lime
3305	3381	lime and shale
3381	3385	lime and shale T.D.

Tops.		
Heebner shale	2969	(-11041)
Base Oread	3001	(-1073)
Brown Lime	3072	(-1144)
Lansing	3092	(-1164)
Sooy Cong.	3362	(-1434)
Arbuckle	3381	(-1453)

State of Kansas.)
)
 County of Sedgwick.) ss

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well and further affiant saith not.

J. B. Hinkle

Subscribed and sworn to before me this 2nd day of March, 1951.

Muriel A. Lepton
 N.P.

My commission expires 1-17-54.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 12 1957
 REGISTRATION DIVISION

PLUGGING
 FILE SEC 21 T 16 R 11W
 BOOK PAGE 44 LINE 45