

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02583-00-00
Spot: SWSESWNW Sec/Twnshp/Rge: 23-26S-14E
2805 feet from S Section Line, 4325 feet from E Section Line
Lease Name: SCHAFFER Well #: 3AO
County: WOODSON Total Vertical Depth: 1285 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1253		65 SX
SURF	8	200		48 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2016 2:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 228-2847

Proposed Plugging Method: RIH W/ 2 3/8" TBG TO TD, "GEL" HOLE UP (MIX BENTONITE & WTR, PMP & CIRC SAME TO SURF), PMP 200' CMT PLUG ON BTM, PU TBG TO 1070', PMP IN A 50' CMT PLUG, PU TBG TO 700', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP CMT TO SURF, POOH TBG, TOP WELL OFF W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP LOCATION.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 12/02/2016 3:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1285', pumped 200' cement plug, pulled tubing to 1078', pumped 50' cement plug, pulled tubing to 713', pumped 50' cement plug, pulled tubing to 250', circ. Cement to surface. gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1253	1274		
RECEIVED KCC DIST # 3 DEC 12 2016 CHANUTE, KS mtt KCC WICHITA DEC 15 2016			

Remarks:

Plugged through: TBG

RECEIVED
12-15-16

District: 03

Signed Mike Heffern
(TECHNICIAN)

DEC 21 2016