

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-01723-00-00  
Spot: NESESWNW Sec/Twnshp/Rge: 23-26S-14E  
2065 feet from N Section Line, 1020 feet from W Section Line  
Lease Name: SCHAFFER Well #: 1-A  
County: WOODSON Total Vertical Depth: 1256 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1255		60 SX
SURF	7	286		48 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/02/2016 3:00 PM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: \_\_\_\_\_ Phone: (913) 236-0016

Proposed Plugging Method: RIH 2 3/8" TBG TO TD, "GEL" WELL UP (PMP IN MIX OF BENTONITE & WTR TO SURF), THEN PMP IN A 200' CMT PLUG ON BTM, PU TBG TO 1070', PMP IN 50' CMT PLUG, PU TBG TO 700', PMP IN 50' CMT PLUG, PU TBG TO 250', PMP IN CMT TO SURF, POOH TBG, "TOP WELL OFF" W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", CLEAN UP LOCATION.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE  
Date/Time Plugging Completed: 12/02/2016 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1256', pumped 200' cement plug, pulled tubing to 1085' pumped 50' cement plug, pulled tubing to 713' pumped 50' cement plug, pulled tubing to 250' circ. Cement to surface, gel sacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1229	1239		

RECEIVED  
KCC DIST # 3  
DEC 12 2016  
CHANUTE, KS  
MH  
KCC WICHITA  
DEC 15 2016  
RECEIVED

Remarks:

Plugged through: TBG

12-15-16

District: 03

Signed Mick Heffern  
(TECHNICIAN)

DEC 21 2016