

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22134-00-00
Spot: N2S2NE Sec/Twnshp/Rge: 23-11S-23W
3630 feet from S Section Line, 1320 feet from E Section Line
Lease Name: SDA Well #: 1
County: TREGO Total Vertical Depth: 4070 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4068		160 SX
SURF	8.625	262		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2016 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: CURTIS R LONGPINE Company: DAMAR RESOURCES Phone: (785) 625-0020

Proposed Plugging Method: Ordered 525 sx 60/40 pozmix 4% gel cement w/ 700 # hulls.
Port collar @ 1780 210 sx
Perforations: 3561'-64', 3629'-32', 3714'-18', 3796'-98'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2016 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3720' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 3212' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 2256' and pumped 200 sx cement w/200 # hulls. Good circulation of cement. Pulled tubing. Topped off casing with 45 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 200 psi.


GPS: 39.08351 -099.83801

Remarks: QUALITY CEMENT TICKET # 3071

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

KCC WICHITA

NOV 29 2016

RECEIVED

NOV 21 2016

DEC 21 2016

Form CP-2/3