

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24765-00-00
Spot: NENWNWSE Sec/Twnshp/Rge: 9-20S-21W
2639 feet from S Section Line, 2268 feet from E Section Line
Lease Name: KB UNIT Well #: 1
County: NESS Total Vertical Depth: 4520 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1496		WITH 125 SX CMT
PROD	5.5	4517	0	WITH 100 SX CMT
SURF	8.625	690		WITH 280 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2016 8:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Revd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-3145

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. SPACER TO 1500' THEN CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2016 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4461' & PUMPD 25 SX GEL IN 55 BBL WATER THEN 40 SX CMT & 200# HULLS. PULLED TBG TO 1500' & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4442	4450		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

JA

RECEIVED
DEC 06 2016
KCC DODGE CITY

DEC 21 2016

Form CP-2/3