

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20741-00-00
Spot: NENWNENW Sec/Twnshp/Rge: 28-4S-22W
85 feet from N Section Line, 1895 feet from W Section Line
Lease Name: S & B Well #: 1
County: NORTON Total Vertical Depth: 3743 feet

Operator License No.: 34916
Op Name: FOURWINDS OIL CORPORATION
Address: PO BOX 1063
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	233		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/18/2016 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

KCC WICHITA
DEC 14 2016
RECEIVED

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 11/18/2016 3:00 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st plug @3705 w/50 sx
2nd plug @1940 w/50 sx
3rd plug @1150 w/100 sx
4th plug @300 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Ed Schumacher
(TECHNICIAN) CM

NOV 20 2016

[Signature]
DEC 21 2016