

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21696-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 1-23S-31W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: TREKELL Well #: 3-1
County: FINNEY Total Vertical Depth: 4870 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4615		
CIBP		4778		
DVT	5.5	1847		WITH 230 SX CMT
PROD	5.5	4845	0	WITH 380 SX CMT
SURF	8.625	306		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2016 11:00 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Revd. from: ARNOLD HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2016 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT & 150# HULLS AT 4517'. CIRCULATE CMT FROM 1919' TO SURFACE WITH 190 SX CMT. TOOH WITH TBG & TOP OFF WITH 30 SX CMT. STAYED FULL. PUMP 10 SX CMT DOWN THE ANNULUS TO 300 PSI.

Perfs:


Top	Bot	Thru	Comments
4786	4789		
4757	4767		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
DEC 06 2016
KCC DODGE CITY

Form CP-2/3

DEC 21 2016