

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-20038-00-00
Spot: W2W2NE Sec/Twnshp/Rge: 20-18S-11W
3960 feet from S Section Line, 2310 feet from E Section Line
Lease Name: STRAUB Well #: 1
County: BARTON Total Vertical Depth: 3404 feet

Operator License No.: 9951
Op Name: KRIER, KIRBY OIL, INC.
Address: 1043 NE 80TH RD
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3392		100 SX
SURF	8.62	255		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2016 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KIRBY KRIER Company: KRIER, KIRBY OIL, INC. DBA Phone: (620) 562-7637

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls.

KCC WICHITA
DEC 14 2016
RECEIVED

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350' and 660'. Ran tubing to 3328' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 2300' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 1350' and pumped 50 sx cement. Pulled tubing to 660'. Circulated cement to surface with 60 sx cement and 100 # hulls. Pulled tubing. Topped off casing with 10 sx cement pressured to 250 psi. Tied on to surface pipe and pumped 20 sx cement pressured to 300 psi.

GPS: 38.47464 -098.56243

Perfs:

Top	Bot	Thru	Comments
3392	3397		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

[Signature] CM

Form CP-2/3

DEC 21 2016