

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21189-00-00
Spot: SWSWNESE Sec/Twnshp/Rgc: 28-16S-34W
1630 feet from S Section Line, 1110 feet from E Section Line
Lease Name: WESSELER Well #: 3-28
County: SCOTT Total Vertical Depth: 4855 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 1616 S VOSS RD STE 600
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290		WITH 190 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/06/2016 11:00 PM
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.
Proposal Rcvd. from: CHRIS Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: 1ST PLUG AT 2470' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 725' WITH 50 SX CMT. 4TH PLUG AT 320' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2016 1:00 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

1ST PLUG AT 2470' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 725' WITH 50 SX CMT. 4TH PLUG AT 320' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
DEC 08 2016
KCC DODGE CITY

DEC 21 2016

Form CP-2/3