

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-20969-00-00
Spot: NE Sec/Twnshp/Rge: 3-32S-39W
3938 feet from S Section Line, 1423 feet from E Section Line
Lease Name: COXON Well #: 3-26
County: STEVENS Total Vertical Depth: 2950 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2950	0	WITH 410 SX CMT
SURF	8.625	693		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/22/2016 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: WELL IS SANDED IN TO 2200'. PLUG AT 2200' WITH 80 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 750' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2016 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

WELL IS SANDED IN TO 2200'. 1ST PLUG AT 2176' WITH 80 SX CMT. 2ND PLUG AT 1500' WITH 200# HULLS & 50 SX CMT. LOAD & TEST CASING TO 400 PSI. HOLDING. 3RD PLUG AT 750' WITH 75 SX CMT TO 0'. CHECK BACKSIDE WITH 25 SX CMT TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2382	2709		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Kenny M. Sullivan

(TECHNICIAN)

SR

RECEIVED
NOV 23 2016

KCC DODGE CITY

Form CP-2/3

Man
DEC 21 2016