

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26009-00-00
Spot: SWSWSENE Sec/Twnshp/Rge: 32-16S-13W
2320 feet from N Section Line, 1125 feet from E Section Line
Lease Name: REIDL Well #: 2
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3430	1994	160 SX
SURF	8.625	514		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2016 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS Phone: (785) 445-2353

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Pulled 1994' of 5 1/2' casing leaving 1436' of casing in the hole.

KCC WICHITA
DEC 14 2016
RECEIVED

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2016 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

11/22/2016- Sanded off perforations and bailed 5 sx cement. Top of cement at 3225'. Cut casing at 1994'. Pulled casing to 1400'.
11/23/2016- Hooked to casing and pumped 125 sx cement w/200 # hulls. Pulled casing to 850' and pumped 50 sx cement w/100 # hulls. Pulled casing to 550' and pumped 75 sx cement w/100 # hulls. Pulled casing to 200' and pumped 75 sx cement. Circulated cement to the pit. POOH and cellar stayed full of cement.
GPS: 38.61701 -098.77962

Perfs:

Top	Bot	Thru	Comments
3356	3358		

Remarks: QUALITY CEMENTING TICKET # 3080

Plugged through: CSG

District: 04

Signed Ray Dinkel
(TECHNICIAN)

CM

NOV 28 2016

DEC 21 2016