

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21196-00-00
Spot: NESE Sec/Twnshp/Rge: 18-31S-34W
2181 feet from S Section Line, 658 feet from E Section Line
Lease Name: BAUGHMAN F Well #: 2-18
County: SEWARD Total Vertical Depth: 5775 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4520		WITH 2 SX CMT
DVT		3226		WITH 225 SX CMT
PROD 5.5		4828	1746	WITH 150 SX CMT
SURF 8.625		1692		WITH 650 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2016 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: CIBP @ 4520' WITH 2 SX CMT. PLUG AT 1730' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2016 11:30 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

11/21/16: CIBP @ 4520' WITH 2 SX CMT. 1ST PLUG AT 1735' WITH 50 SX CMT. 2ND PLUG AT 575' WITH 50 SX CMT. LOST CIRCULATION. 11/22/16: TOC @ 900'. 2ND PLUG AT 569' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4568	4572		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
DEC 06 2016
KCC DODGE CITY

SA

DEC 21 2016

Form CP-2/3