

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-067-20518-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 12-27S-35W  
2707 feet from S Section Line, 2893 feet from E Section Line  
Lease Name: LANDER C Well #: 2  
County: GRANT Total Vertical Depth: 3029 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL RD STE 1200  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		850		
PROD	4.5	3028	0	WITH 275 SX CMT
SURF	8.625	805		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2016 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/15/2016 11:00 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

Perfs:

CUT @ 1925'. TBG NOT FREE, TAKING FLUID, PUMPED 35 SX CMT. CUT TBG AT 1000'. SET CIBP @ 850'. PERFORATE AT 830'. CIRCULATE TO SURFACE WITH 260 SX CMT	Top	Bot	Thru	Comments
	2850	2912		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
NOV 18 2016  
KCC DODGE CITY

DEC 21 2016

Form CP-2/3