

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21600-00-00
Spot: E2W2E2 Sec/Twnshp/Rge: 9-15S-28W
2640 feet from S Section Line, 1650 feet from E Section Line
Lease Name: ROBERTS E Well #: 1-9
County: GOVE Total Vertical Depth: 4300 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4298		225 SX
SURF	8.625	305		200 SX
TI	2.375	3870		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2016 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: MONTE Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Port Collar at 1960' w/300 sx cement.
Perforations: 3702'-04', 3802'-04', 3831'-33', 3843'-46', 3895'-98'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2016 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3823' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 3245' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 2545' and pumped 100 sx cement. Pulled tubing to 1095' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 20 sx cement. Tied on to backside and squeezed with 40 sx cement. Shut in pressure 250 psi.

GPS: 38.76438 -100.43559

Perfs:

Top	Bot	Thru	Comments
3895	3898		
3843	3846		
3831	3833		
3802	3804		
3702	3704		

Remarks: SWIFT CEMENT TICKET # 29498

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

KCC WICHITA

NOV 29 2016

RECEIVED

DEC 21 2016

Form CP-2/3